


USE TYPEWRITER OR BALL  
POINT PEN—PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment—Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Kearny</b>	Fraction <b>SW 1/4 SW 1/4 SW 1/4</b>	Section number <b>10</b>	Township number <b>T 25 S R 36 E (W)</b>	Range number
2. Distance and direction from nearest town or city: <b>2 1/2 S. &amp; 3/4 W. of Lakin</b> Street address of well location if in city:				3. Owner of well: <b>Forrest Puckett</b> R.R. or street: <b>Box 312</b> City, state, zip code: <b>Lakin, KS 67860</b>		
4. Locate with "X" in section below: <div style="text-align: center;">N 1 Mile W 1 Mile E S 1 Mile</div> 				Sketch map:		
5. Type and color of material				From	To	6. Bore hole dia. <b>26</b> in. Completion date <b>4/15/76</b> Well depth <b>197</b> ft.
See attachment						7. Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
						8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
						9. Casing: Material <b>Steel</b> Height (Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>36</b> lbs./ft. Dia. <b>18</b> in. to <b>141</b> ft. depth Wall Thickness: inches or Dia. <b>20</b> in. to <b>197</b> ft. depth gage No. <b>219</b>
						10. Screen: Manufacturer's name _____ Type <b>Torch perf.</b> Dia. <b>20" &amp; 18"</b> Slot/gauze <b>3/16</b> Length <b>197'</b> Set between <b>0</b> ft. and <b>197</b> ft. Gravel pack? <b>Yes</b> Size range of material <b>1/4 x 1/8</b>
						11. Static water level: <b>15</b> ft. below land surface Date <b>4/15/76</b>
						12. Pumping level below land surface <b>Not pumped</b> _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.
						13. Water sample submitted: _____ mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date _____
						14. Well head completion: <b>12</b> inches above grade Pitless adapter _____
						15. Well grouted? <b>Yes</b> With: _____ Neat cement <input checked="" type="checkbox"/> Bentonite _____ Concrete _____ Depth: From <b>0</b> ft. to <b>10</b> ft.
						16. Nearest source of possible contamination: <b>None observed</b> ft. _____ Direction _____ Type _____ Well disinfected upon completion? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
						17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
(Use a second sheet if needed)						
18. Elevation: <b>Flat</b> Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Henkle Drilling &amp; Supply 145</b> Business name _____ License No. _____ Address <b>Box 639 Garden City</b> Signed <b>Jim Henkle</b> Date <b>5/12/76</b> Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

HENKLE DRILLING & SUPPLY COMPANY, INC.

Bill Pilot      Reamer

Hours: 534      Air Comp.

W/O. 4878

CUSTOMER Forrest Puckett

County Kearny Sec. 10 Twp 25 Range 36

Depth		Time Record		Remarks	Water
Date	From To	Start	Finish		
				DONT NEED TO TYPE	
0	3	0	34	SAND & GRAVEL	
		34	48	BROWN CLAY	
		48	54	SAND & GRAVEL	
		54	82	SAND & GRAVEL Lots of CLAY	
		82	95	BROWN CLAY	
		95	102	SAND & GRAVEL Brown Clay St	
		102	106	BROWN CLAY few Sand St	
		106	130	SAND & GRAVEL Lots of CLAY	
		130	156	SAND & GRAVEL (Good)	
		156	176	BROWN CLAY FIRM	
		176	180	SAND & GRAVEL (Good)	
		180	190	BROWN CLAY (FIRM)	
		190	196	SAND & GRAVEL (Good)	
		196	199	BROWN CLAY (FIRM)	
				TOTAL Depth 199'	

Total Gallons Used \_\_\_\_\_