

DRILLERS TEST LOG

CUSTOMERS NAME Howard Rexroat DATE May 7, 1985
STREET ADDRESS P. O. Box 43 TEST # 1 E. LOG yes
CITY & STATE Lakin, KS 67860 DRILLER Livingston
COUNTY Kearny QUARTER NE SECTION 16 TOWNSHIP 25 RANGE 36
LOCATION 1320' South and 450' east of the NW corner of 1/4

| % | FOOTAGE | | | DESCRIPTION OF STRATA | Static Water Level |
|----|---------|-----|-----|--|---------------------|
| | From | Pay | To | | Proposed Well Depth |
| | 0 | | 1 | Top soil | |
| | 1 | | 20 | Sand fine to medium, small to large gravel few cobble stones | |
| | 20 | | 25 | Brown clay | |
| | 25 | | 28 | Sand fine to medium, small to medium gravel | |
| | 28 | | 80 | Brown sandy clay, limerock ledges and few sand streaks | |
| | 80 | | 100 | Brown clay | |
| | 100 | | 123 | Very fine sand and clay streaks | |
| | 123 | | 128 | Sand fine to medium, coarse, small gravel | |
| | 128 | | 140 | Blue clay | |
| 65 | 140 | 10 | 150 | Sand fine to medium, coarse, small to medium gravel | |
| | 150 | | 165 | Brown sandy clay limerock | |
| 65 | 165 | 15 | 180 | Sand fine to medium, coarse, small gravel | |
| | 180 | | 203 | Brown sandy clay | |
| 50 | 203 | 09 | 212 | Sand fine to medium, coarse | |
| | 212 | | 230 | Brown clay | |
| 45 | 228 | 15 | 243 | Sand fine to medium, few coarse. | |
| | 243 | | 280 | Brown clay limerock | |
| | | | | | |
| | | | | | |
| | | | | 5" PVC | |
| | | | | Perf Plain | |
| | | | | 245'-230' 15' | |
| | | | | 230'-210' 20' | |
| | | | | 210'-200' 10' | |
| | | | | 200'-180' 20' | |
| | | | | 180'-160' 20' | |
| | | | | 160'-150' 10' | |
| | | | | 150'-140' 10' | |
| | | | | 140'-0 140' | |
| | | | | Total 55' 190' | |
| | | | | | |
| | | | | #1 fine gravel pack | |
| | | | | 200# Celca | |
| | | | | 2-5" Caps | |
| | | | | 2-Buckets pellets at 100' | |
| | | | | 1-5" Collar | |
| | | | | | |
| | | | | | |
| | | | | | |

GARDEN CITY, KS
Phone 276-3278

HENKLE DRILLING & SUPPLY CO., INC.
IRRIGATION HEADQUARTERS

SUBLETTE, KS
Phone 675-4311

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * STOCK WELLS