


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

#33

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>KEARNY</u>	Fraction <u>NW 1/4 SE 1/4 NW 1/4</u>	Section number <u>23</u>	Township number <u>T 25 S R 36</u>	Range number <u>1/W</u>
2. Distance and direction from nearest town or city: <u>4 south, 1/2 east</u> <u>1/2 south of Lakin, Ks.</u> Street address of well location if in city:				3. Owner of well: <u>Minter-Wilson Drilling Co.</u> R.R. or street: <u>Box A</u> City, state, zip code: <u>Garden City, Ks. 67846</u>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>26</u> in. Completion date <u>2-29-76</u> Well depth <u>381</u> ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☒ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material <u>steel</u> Height: Above or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>36.87</u> lbs./ft. Dia. <u>16</u> in. to <u>382</u> ft. depth Wall thickness: inches or Dia. <u>16</u> in. to <u>382</u> ft. depth gage No. <u>219 m/c</u>		
				10. Screen: Manufacturer's name <u>Johnson Division</u> Type <u>Galv.</u> Dia. <u>16"</u> Slot/gauze <u>100</u> Length <u>20'</u> Set between <u>290-300</u> ft. and <u>340-350</u> <u>150-290</u> ft. and <u>300-340-350-381</u> Gravel pack? <u>yes</u> Size range of material <u>1/2" down</u>		
				11. Static water level: <u>62</u> ft. below land surface Date <u>2-14-76</u>		
				12. Pumping level below land surfaces: <u>170</u> ft. after <u>3</u> hrs. pumping <u>1325</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>1325</u> g.p.m.		
				13. Water sample submitted: <u> </u> mo./day/yr. Yes ☒ No ☐ Date <u> </u>		
				14. Well head completion: <u>12</u> inches above grade ☐ Pitless adapter ☒ <u>yes</u>		
				15. Well grouted? <u>yes</u> With: ☐ Neat cement ☒ Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
				16. Nearest source of possible contamination: <u>N/A</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <u> </u> Yes ☒ No ☐		
				17. Pump: ☐ Not installed Manufacturer's name <u>Goulds US Pumps</u> Model number <u>12 JHC</u> HP <u>100</u> Volts <u> </u> Length of drop pipe <u>160</u> ft. capacity <u>1000</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
		(Use a second sheet if needed)				
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief <u>Minter-Wilson Drilling Co.</u> Business name <u>P.O. Box A Garden City, Ks.</u> License No. <u> </u> Address <u> </u> Signed <u> </u> Date <u>8-3-76</u> Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment
Water Section

Form WWC-5

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

Minter-Wilson. ✓

Kearney County

191 23-25-36

14-2-73

Rivet 5 offset 250' E

Static water level 80

Circle 5

Circle #33

0	21	Top soil
21	57	Sand & gravel
57	66	Sandy clay - sand & gravel
66	132	sandy clay- sand& gravel streaks
132	260	Sand & gravel sandy clay streaks 10%
60	344	Sandy clay fine to med sand & gravel
74	360	Sand & gravel fine med
60	435	Fine med sand & gravel sandy clay 20%
35	440	Yellow clay