


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County KEARNY	Fraction NE 1/4 SW 1/4 NW 1/4	Section number 21	Township number T 25 S	Range number R 36 E
2. Distance and direction from nearest town or city: 4 south, 2 east, 1/4 south of Lakin, Ks. Street address of well location if in city:			Name of well: Minter -Wilson Drilling Co. R.R. or street: Box A City, state, zip code: Garden City, Ks. 67846			
4. Locate with "X" in section below: 			Sketch map:		6. Bore hole dia. 26 in. Completion date 1-26-76 Well depth 380 ft.	
5. Type and color of material			From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
					8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
					9. Casing: Material steel Height: 12 ft. Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 36.87 lbs./ft. Dia. 16 in. to 381 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 219 MAC	
					10. Screen: Manufacturer's name JOHNSON DIVISION Type Galv. Dia. 16" Slot/gauze 100 Length 20' Set between 210-250 ft. and 365-375 ft. Perf. 120-240 ft. and 250-265, 375-380 ft. Gravel pack? yes Size range of material 1/2" Down	
					11. Static water level: ☐ mo./day/yr. 71 ft. below land surface Date 1-26-76	
					12. Pumping level below land surfaces: 115 ft. after 3 hrs. pumping 1400 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1400 g.p.m.	
					13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐	
					14. Well head completion: 12 ☐ Pitless adapter ☐ Inches above grade	
					15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From ☐ ft. to 10 ft. N/A	
					16. Nearest source of possible contamination: ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No	
					17. Pump: ☐ Not installed Manufacturer's name Goulds US Pumps Model number 12 JHC HP 100 Volts ☐ Length of drop pipe 160 ft. capacity 1000 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation:			19. Remarks:			
Topography: ☒ Hill ☐ Slope ☐ Upland ☐ Valley			(Use a second sheet if needed)			
			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Minter Wilson Drilling 208 Business name P.O. Box A Garden City, Ks. Address Box A Signed M. Wilson 8-3-76 Authorized representative Date			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

professionals

MINTER-WILSON DRILLING CO.

INCORPORATED

and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269

P.O. Box 493

GARDEN CITY, KANSAS 67846

Minter-Wilson

CHUCK JAEGER
Kearny County
11-19-75

Location: NE 24-25-36
Pivot 36, 30 feet East of Pivot

Static Water Level 80'

0	1	Top Soil
1	10	Fine Sand
10	20	Fine to Med. Sand
20	45	Med. Coarse Gravel
45	56	Brown Sandy Clay
56	80	Med. Coarse Gravel
80	150	Med. Sand Gravel, Clay Streaks
150	155	Brown Sandy Clay
155	159	Med. Coarse Gravel
159	166	Brown Sandy Clay
166	173	Med. Coarse Gravel
173	177	Brown Sandy Clay
177	200	Med. Coarse Gravel, Clay Streaks
200	211	Fine to Med. Sand & Gravel Streaks
211	231	Brown Sandy Clay
231	240	Med. Sand & Gravel (Loose)
240	264	Fine to Med. Sand & Gravel, Clay Streaks
264	362	Brown Sandy Clay
362	380	Fine to Med. Sand & Gravel
380	400	Brown Sandy Clay, Gravel Streaks
400	430	Yellow Clay

T.D. 380'