

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

County KEARNY		Fraction SW 1/4 NE 1/4 SW 1/4		Section number 24		Township number T 25 S		Range number R 36 E/W	
1. Location of well: 3/4 south, 1 1/2 east of Lakin, Ks. Street address of well location if in city:				3. Owner of well: Minter-Wilson Drilling Co. R.R. or street: Box A City, state, zip code: Garden City, Ks. 67846					
4. Locate with "X" in section below: N 1 Mile W 1 Mile E S				Sketch map:		6. Bore hole dia. 26 in. Completion date 1-26-76 Well depth 405 ft.			
5. Type and color of material				From		To		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
								8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
								9. Casing: Material <u>steel</u> Height: Above or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>36.87</u> lbs./ft. Dia. <u>16</u> in. to <u>106</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u> </u>	
								10. Screen: <u>Johnson Division</u> Type <u>Galv.</u> Dia. <u>16"</u> Slot/gauze <u>100</u> Length <u>20'</u> Set between <u>360</u> ft. and <u>380</u> ft. Pef. <u>140-360</u> ft. and <u>380-405</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/2" Down</u>	
								11. Static water level: <u> </u> mo./day/yr. <u>70</u> ft. below land surface Date <u>2-9-76</u>	
								12. Pumping level below land surface: <u>35</u> ft. after <u>3</u> hrs. pumping <u>1400</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>1400</u> g.p.m.	
								13. Water sample submitted: <u> </u> mo./day/yr. <u> </u> Yes ☒ No ☐ Date <u> </u>	
								14. Well head completion: <u>12</u> <u> </u> Pitless adapter <u> </u> inches above grade	
								15. Well grouted? <u>yes</u> With: <u> </u> Neat cement <u> </u> Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft. <u>N/A</u>	
								16. Nearest source of possible contamination: ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <u> </u> Yes ☒ No ☐	
(Use a second sheet if needed)						17. Pump: <u>Not installed</u> Manufacturer's name <u>Goulds US Pumps</u> Model number <u>12JHC</u> HP <u>100</u> Volts <u> </u> Length of drop pipe <u>160</u> ft. capacity <u>1000</u> g.p.m. Type: <u> </u> Submersible ☒ Turbine <u> </u> Jet <u> </u> Reciprocating <u> </u> Centrifugal <u> </u> Other			
						18. Elevation:		19. Remarks:	
						Topography: ☒ Hill ☐ Slope ☐ Upland ☐ Valley			
						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Minter Wilson Drilling 208</u> Business name <u>P.O. Box A Garden City, Ks.</u> Address <u> </u> Signed <u> </u> Date <u>8-3-76</u> Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

professionals

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 276-8269 • P.O. Box 493 • GARDEN CITY, KANSAS 67846

Winter-Wilson ✓

Kearny County

S.N. 24-25-36

10-3-75

Static water level 30
Circle 12

Circle #39

0	10	Top soil
10	60	Fine med sand & gravel
60	112	Fine med sand & gravel sandy clay 20%
112	195	Fine med sand & gravel sandy clay 10%
195	280	Sandy clay fine med sand & gravel
280	300	Fine med sand & gravel (loose)
300	322	Sandy clay
322	405	Fine med sand & gravel sandy clay 10%
405	420	Yellow & blue clay

ED 405