

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 047 KEARNEY SE 1/4 SE 1/4 SE 1/4 29 T 25 S R 36 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 6 MILES SOUTH AND 2 WEST OF LAKIN.

2 WATER WELL OWNER: LAKIN FEED YARD
 RR#, St. Address, Box #: P.O. BOX 1026 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : LAKIN, KS 67860- Application Number: 39,593

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12

4 DEPTH OF COMPLETED WELL 478 ELEVATION:
 Depth(s) Groundwater Encountered 1. 130 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 130 ft. below land surface measured on mo/day/yr 06/26/91
 Pump test data: Well water was ft. after hours pumping gpm
 Estimated Yield gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 10 in. to 478 ft., and in. to ft.
 WELL WATER TO BE USED AS: 03 FEEDLOT
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 478 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 198 ft. to 238 ft., From 378 ft. to 398 ft. 458 ft. to 478 ft.
 From 338 ft. to 358 ft., From 418 ft. to 438 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 90 ft., From ft. to ft.
 From 100 ft. to 478 ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 8 ft. to 25 ft., From 90 ft. to 100 ft., From ft. to ft.
 What is the nearest source of possible contamination: 09 FEEDYARD
 Direction from well? LOCAL AREA How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	14	06 VERY FN SAND 07 FINE SAND			
14	30	07 FINE SAND 08 MEDIUM SAND 04 SANDY CLAY			
30	58	08 MEDIUM SAND 13 FINE GRAVEL 15 CRS GRAVEL			
58	60	01 CLAY			
60	84	08 MEDIUM SAND 13 FINE GRAVEL 15 CRS GRAVEL			
84	139	01 CLAY 05 SAND			
139	190	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
190	205	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
205	218	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL			
218	225	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/27/91 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/11/91
 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas B. Henkle*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 047 KEARNEY SE 1/4 SE 1/4 SE 1/4 29 T 25 S R 36 W

2 WATER WELL OWNER: LAKIN FEED YARD

RR#, St. Address, Box #: P.O. BOX 1026

Board of Agriculture, Division of Water Resources

City, State, ZIP code : LAKIN, KS 67860-

Application Number: 39,593

FROM	TO	LITHOLOGIC LOG
225	235	07 FINE SAND 08 MEDIUM SAND 13 FINE GRAVEL
235	260	04 SANDY CLAY 20 LIMESTONE 23 SANDSTONE
260	280	04 SANDY CLAY 07 FINE SAND 20 LIMESTONE
280	316	01 CLAY
316	350	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
350	370	01 CLAY
370	478	23 SANDSTONE
478	485	28 ROCK
485	495	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 06/27/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/11/91 under the business name of HENKLE DRILLING & SUPPLY by (signature)

Douglas B. Henkle