

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 047 KEARNY SE 1/4 NE 1/4 SE 1/4 29 T 25 S R 36 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 5 1/2 MILES SOUTH AND 1 MILE WEST OF LAKIN.

2 WATER WELL OWNER: LAKIN FEED YARD, INC.

RR#, St. Address, Box #: P.O. BOX 1026

Board of Agriculture, Division of Water Resources

City, State, ZIP code : LAKIN, KS 67860-

Application Number: 39,594

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

1	2	3	4
5	6	7	8
9	10	11	12
13	14	15	16
17	18	19	20
21	22	23	24
25	26	27	28
29	30	31	32
33	34	35	36
37	38	39	40
41	42	43	44
45	46	47	48
49	50	51	52
53	54	55	56
57	58	59	60
61	62	63	64
65	66	67	68
69	70	71	72
73	74	75	76
77	78	79	80
81	82	83	84
85	86	87	88
89	90	91	92
93	94	95	96
97	98	99	100

4 DEPTH OF COMPLETED WELL 505 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 130 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 130 ft. below land surface measured on mo/day/yr 09/05/91
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm; Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 9.875 in. to 505 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 03 FEEDLOT

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC

CASING JOINTS: GLUED

Blank casing diameter 5 in. to 505 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265

TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC

SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 205 ft. to 225 ft., From 305 ft. to 325 ft.

From 245 ft. to 265 ft., From 345 ft. to 365 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 85 ft., From 0 ft. to 0 ft.

From 95 ft. to 505 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE

Grout Intervals: From 5 ft. to 25 ft., From 85 ft. to 95 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: 09 FEEDYARD

Direction from well? LOCAL AREA

How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	11	06 VERY FN SAND 07 FINE SAND			
11	19	06 VERY FN SAND 07 FINE SAND 04 SANDY CLAY			
19	85	08 MEDIUM SAND 17 SAND & GRAVL 15 CRS GRAVEL			
85	100	01 CLAY 05 SAND			
100	126	01 CLAY 05 SAND			
126	140	01 CLAY 05 SAND			
140	233	17 SAND & GRAVL 23 SANDSTONE 01 CLAY			
233	255	01 CLAY 20 LIMESTONE 05 SAND			
255	275	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
275	297	01 CLAY 20 LIMESTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/07/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/06/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas R. Henkle*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 047 KEARNY SE 1/4 NE 1/4 SE 1/4 29 T 25 S R 36 W

2 WATER WELL OWNER: LAKIN FEED YARD, INC.

RR#, St. Address, Box #: P.O. BOX 1026

Board of Agriculture, Division of Water Resources

City, State, ZIP code : LAKIN, KS 67860-

Application Number: 39,594

SCREEN PERFORATED INTERVALS: From 405 ft. to 425 ft., From 485 ft. to 505 ft.
From 445 ft. to 465 ft., From 0 ft. to 0 ft.

FROM	TO	LITHOLOGIC LOG
297	305	01 CLAY 07 FINE SAND
305	322	06 VERY FN SAND 07 FINE SAND 01 CLAY
322	330	01 CLAY
330	340	07 FINE SAND 08 MEDIUM SAND
340	350	01 CLAY
350	365	06 VERY FN SAND 07 FINE SAND
365	370	01 CLAY
370	459	23 SANDSTONE
459	472	28 ROCK 23 SANDSTONE
472	485	19 SHALE 28 ROCK
485	505	23 SANDSTONE
505	510	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/07/91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 02/06/92 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Douglas A. Henkle*