

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 047 KEARNY | NW 1/4 NW 1/4 NW 1/4 | 02 | T 25 S | R 36 W

Distance and direction from nearest town or city street address of well if located within city?

FROM LAKIN; APPX 1 MILE SOUTH

2 WATER WELL OWNER: RICHARD BAYLIFF
 RR#, St. Address, Box #: PO BOX 1004 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: GUYMON, OK 73802-1004 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 200 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 21 ft. below land surface measured on mo/day/yr 07/28/06
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 10 in. to 200 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: 01 DOMESTIC
Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: OTHER - CERTILOK
 Blank casing diameter 5 in. to 200 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 160 ft. to 200 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 200 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	44	05 SAND 11 GRAVEL			
44	51	04 SANDY CLAY			
51	122	05 SAND 11 GRAVEL 01 CLAY			
122	137	04 SANDY CLAY			
137	200	05 SAND 11 GRAVEL 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/18/06 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 10/20/06
 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Brian J. Richman*