

19.156

Check: ☒ White Copy, ☐ Blue Copy, ☐ Pink Copy

The
Professionals

MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation
and Domestic
Water Systems
Complete Installation
and Repairing

Phone 620-276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

NAME BRENT TOKOI - CIRCLE # T9
COUNTY KEARNY
DATE 8-26-10

LOCATION: NW 1/4 36-25-36 - FROM LAKIN LANE & PARALLEL ROAD-
1 1/2 MILE EAST, 1 MILE NORTH AND
1/2 MILE WEST
- NORTHWEST EDGE OF CIRCLE

STATIC WATER LEVEL -

TEST # 1

0' TO 10' - FINE PACKED SAND
10' TO 14' - BROWN SANDY CLAY
14' TO 78' - FINE TO MEDIUM SAND & GRAVEL-SOME COARSE
WITH LAYERS OF BROWN SANDY CLAY
78' TO 85' - BROWN SANDY CLAY
85' TO 91' - GRAY CLAY
91' TO 102' - FINE TO MEDIUM SAND & GRAVEL-SOME COARSE
102' TO 110' - BLUE CLAY
110' TO 145' - FINE TO MEDIUM SAND & GRAVEL-SOME COARSE
WITH LAYERS OF BROWN SANDY CLAY
145' TO 155' - BROWN SANDY CLAY
155' TO 172' - BLUE CLAY
172' TO 194' - FINE TO MEDIUM SAND & GRAVEL
194' TO 245' - BROWN SANDY CLAY
WITH LAYERS OF SAND & GRAVEL 20%
245' TO 259' - FINE TO MEDIUM SAND & GRAVEL
WITH STRIPS OF BROWN SANDY CLAY 10%
259' TO 277' - BROWN SANDY CLAY WITH LAYERS OF SAND 30%
277' TO 338' - BROWN SANDY CLAY WITH STRIPS OF WHITE ROCK
AND A FEW STRIPS OF SAND
338' TO 347' - FINE TO MEDIUM SAND & GRAVEL
WITH STRIPS OF BROWN SANDY CLAY 10%
347' TO 359' - BROWN SANDY CLAY WITH STRIPS OF SAND & GRAVEL 15%
359' TO 384' - FINE TO MEDIUM SAND AND GRAVEL
WITH STRIPS OF BROWN SANDY CLAY 20%
384' TO 412' - BROWN SANDY CLAY
412' TO 419' - LOOSE BROWN ROCK
419' TO 433' - BROWN ROCK WITH LAYERS OF BROWN & YELLOW CLAY 30%
433' TO 440' - BROWN AND YELLOW CLAY AND GRAY SHALE
WITH LAYERS OF BROWN ROCK 30%
440' TO 453' - WHITE, YELLOW & BROWN CLAY AND GRAY SHALE
WITH 20% BROWN ROCK
453' TO 476' - SAND STONE WITH SOME WHITE CLAY AND
GRAY SHALE STRIPS 20%
476' TO 485' - SHALE WITH HARD BROWN AND WHITE CLAY- 250 PULL DOWN
485' TO 500' - SHALE - 250 PULL DOWN