

14,278

Check: ☒ White Copy, ☐ Blue Copy, ☐ Pink Copy

*The  
Professionals*

# MINTER-WILSON DRILLING CO.

INCORPORATED

Irrigation  
and Domestic  
Water Systems  
Complete Installation  
and Repairing

Phone 620-276-8269 • P.O. Box A • GARDEN CITY, KANSAS 67846

NAME THREE BO'S, INC.  
COUNTY KEARNY  
DATE 3-12-12

LOCATION: SE 1/4 22-25-36 - LAKIN LANE - 4 MILES SOUTH, 1/8TH OF A MILE WEST & 1/8TH OF A  
MILE NORTH  
- SOUTHEAST EDGE OF CIRCLE

STATIC WATER LEVEL - APPROX. 180 FT.

## TEST # 7

0' TO 15' - FINE SAND  
15' TO 70' - FINE TO MEDIUM SAND & GRAVEL - SOME COARSE  
70' TO 80' - BROWN SANDY CLAY  
80' TO 90' - BROWN CLAY  
90' TO 100' - BLUE CLAY  
100' TO 105' - FINE TO MEDIUM SAND & GRAVEL  
105' TO 160' - BROWN SANDY CLAY WITH LAYERS OF SAND & GRAVEL  
160' TO 167' - FINE TO MEDIUM SAND & GRAVEL  
167' TO 180' - BLUE CLAY  
180' TO 206' - FINE TO MEDIUM SAND & GRAVEL WITH STRIPS OF BROWN SANDY CLAY  
206' TO 215' - BROWN SANDY CLAY  
215' TO 225' - FINE TO MEDIUM SAND & GRAVEL WITH LAYERS OF BROWN SANDY CLAY  
225' TO 276' - BROWN SANDY CLAY  
276' TO 288' - FINE TO MEDIUM SAND  
288' TO 292' - BROWN SANDY CLAY  
292' TO 299' - FINE TO MEDIUM SAND  
299' TO 315' - BROWN SANDY CLAY WITH STRIPS OF SAND - 15%  
315' TO 319' - FINE TO MEDIUM SAND  
319' TO 326' - BROWN SANDY CLAY  
326' TO 330' - FINE TO MEDIUM SAND  
330' TO 337' - BROWN SANDY CLAY  
337' TO 341' - FINE TO MEDIUM SAND & GRAVEL  
341' TO 346' - BROWN SANDY CLAY  
346' TO 360' - FINE TO MEDIUM SAND & GRAVEL WITH STRIPS OF BROWN SANDY CLAY - 15%  
360' TO 381' - BROWN & YELLOW CLAY WITH 20% BROWN ROCK  
381' TO 383' - LOOSE BROWN ROCK  
383' TO 406' - SHALE WITH STRIPS OF BROWN ROCK - 15%  
406' TO 408' - FINE SAND & BROWN ROCK  
408' TO 412' - SHALE  
412' TO 414' - FINE SAND & BROWN ROCK  
414' TO 440' - SHALE WITH 10% WHITE SANDY CLAY BALLS - 250 PULL DOWN  
440' TO 450' - SHALE WITH STRIPS OF SAND STONE - 20% - 250 PULL DOWN  
450' TO 471' - SAND STONE (WHITE SANDY BALLS) & FINE LOOSE SAND  
471' TO 478' - SHALE & SAND STONE LAYERED - 50/50  
478' TO 485' - SHALE WITH STRIPS OF SAND STONE  
485' TO 500' - SAND STONE (FINE SAND & GRAY CHUNKS)  
500' TO 515' - SAND STONE & SHALE - DRILLED TIGHT - 250 PULL DOWN  
515' TO 519' - SAND STONE - LOOSE  
519' TO 526' - SAND STONE - 250 PULL DOWN  
526' TO 543' - SHALE WITH STRIPS OF HARD BLACK ROCK - 300 PULL DOWN  
543' - HARD BLACK ROCK