


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>Hamilton</u>		Fraction <u>NE 1/4 NE 1/4 NE 1/4</u>	Section number <u>21</u>	Township number <u>T 25 S</u>	Range number <u>R 39 E</u>
2. Distance and direction from nearest town or city: <u>Approx. 1 1/2 miles south and 2 1/2 miles west of</u> Street address of well location if in city: <u>kendall, ks.</u>			3. Owner of well: <u>Eldon Hubbard</u> R.R. or street: City, state, zip code: <u>kendall, ks. 67859</u>		
4. Locate with "X" in section below: 		Sketch map:		6. Bore hole dia. <u>2 1/8</u> in. Completion date <u>9/19/79</u> Well depth <u>80</u> ft.	
5. Type and color of material <u>See attached log</u>		From		To	
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☒ Stock ☐ Lawn ☐ Oil field water ☐ Other	
				9. Casing: Material <u>PVC</u> Height: <u>Above</u> or below Threaded ☐ Welded ☐ Surface <u>12</u> in. RMP ☐ PVC ☒ Weight <u>2.9</u> lbs./ft. Dia. <u>5</u> in. to <u>80</u> ft. depth Wall Thickness: inches or Dia. <u>5</u> in. to <u>80</u> ft. depth gage No. <u>265</u>	
				10. Screen: Manufacturer's name <u>Pumpco</u> Type <u>PVC-slotted</u> Dia. <u>5"</u> Slot/gauze <u>0.40</u> Length <u>20'</u> Set between <u>60</u> ft. and <u>80</u> ft. ft. and <u>80</u> ft. Gravel pack? <u>Yes</u> Size range of material <u>#1 Fine</u>	
				11. Static water level: <u>40</u> ft. below land surface Date <u>9/19/79</u> mo./day/yr.	
				12. Pumping level below land surfaces: ft. after <u> </u> hrs. pumping <u> </u> g.p.m. ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>5</u> g.p.m.	
				13. Water sample submitted: <u> </u> mo./day/yr. ☐ Yes ☒ No Date <u> </u>	
				14. Well head completion: ☐ Pitless adapter <u>12</u> inches above grade	
				15. Well grouted? <u>Yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
				16. Nearest source of possible contamination: <u>None</u> ft. <u> </u> Direction <u> </u> Type <u>Observed</u> Well disinfected upon completion? ☒ Yes ☐ No	
				17. Pump: ☒ Not installed Manufacturer's name <u> </u> Model number <u> </u> HP <u> </u> Volts <u> </u> Length of drop pipe <u> </u> ft. capacity <u> </u> g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
				(Use a second sheet if needed)	
18. Elevation: Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Hankle Drilling & Supply Co. 145</u> Business name <u>Garden City, ks. 67846</u> License No. <u> </u> Address <u>Bruce J. Reichmuth</u> Date <u>9/25/79</u> Signed <u> </u> Authorized representative	

25 39 21 NE NE NE
T R Sec 1/4 1/4 1/4

DRILLERS TEST LOG

CUSTOMERS NAME Eldon Hubbard

DATE 9-18-79

STREET ADDRESS

TEST # 1 E. LOG yes

CITY & STATE Kendall, Ks.

DRILLER Rector

COUNTY Hamilton QUARTER NE SECTION 21 TOWNSHIP

25 RANGE 39

LOCATION Near North East corner of quarter

WELL LOCATION

#	DRILLED		FOOTAGE	DESCRIPTION OF STRATA	STATIC WATER LEVEL	
	FROM	PAY				PROPOSED WELL DEPTH
	0		8	Sand		40'
	8		22	Brown Clay & fine sand		
	22		28	Sand fine med. coarse		
	28		58	Brown clay & Calichee		
39	58	2	60	Sand fine med. coarse small gravel		
	60		67	Brown Clay & calichee		
50	67	4	71	Sand fine med. coarse small gravel		
	71		80	Brown Clay & sts. of gyp rock		
	80		90	Blue shale & lime stone very hard		
	90		100	Black shale		80'
				Set 5" PVC		
				80' - 60' Perf.		
				60' - 0' Plain		
				60' Plain		
				20' Perf.		
				80' TOTAL		
				2 yds. #1 fine Smith sand		

MUNNIE DRILLING & SUPPLY CO., INC.

GARDEN CITY, KANSAS

Phone 276-3278

SUBLETTE, KANSAS

Phone 675-4311

TEST HOLES

DOMESTIC WARS

STOCK MARKET

IRRIGATION & INDUSTRIAL WELLS