

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 038 HAMILTON	Fraction NE 1/4 NE 1/4 NW 1/4	Section Number 8	Township Number T 25 S	Range Number R 40 W
---	----------------------------------	---------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM SYRACUSE; APPX 5.2 MILES SOUTH & 1 1/2 MILES EAST

2 WATER WELL OWNER: JEFF WILSON
RR#, St. Address, Box #: PO BOX 941
City, State, ZIP code: SYRACUSE, KS 67878-0941
Board of Agriculture, Division of Water Resources
Application Number:

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

/ \		X		
1	---	NW	---	NE
M	W			E
i				
l				
e				
		SW		SE
\ /				

4 DEPTH OF COMPLETED WELL 420 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 208 ft. below land surface measured on mo/day/yr 03/04/05
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 10 in. to 420 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 420 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS:	From 320 ft. to 420 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 25 ft. to 420 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: NONE OBSERVED
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	23	04 SANDY CLAY			
23	24	20 LIMESTONE			
24	31	31 CALICHE			
31	48	31 CALICHE			
48	187	19 SHALE			
187	211	31 CALICHE 23 SANDSTONE			
211	253	31 CALICHE			
253	291	31 CALICHE 23 SANDSTONE			
291	316	23 SANDSTONE 31 CALICHE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/26/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/30/05
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 038 HAMILTON	NE 1/4 NW 1/4 NW 1/4	8	T 25 S	R 40 W

2 WATER WELL OWNER:	JEFF WILSON	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	PO BOX 941	Application Number:
City, State, ZIP code :	SYRACUSE, KS 67878-0941	

FROM	TO	LITHOLOGIC LOG
316	324	31 CALICHE
324	378	23 SANDSTONE 31 CALICHE
378	418	31 CALICHE 23 SANDSTONE
418	580	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 02/26/05 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/30/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Benny J. Richman*