

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 038 HAMILTON | SE 1/4 SW 1/4 SW 1/4 | 25 | T 25 S | R 43 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM COOLIDGE; APPX 12 3/4 MILES SOUTH & 1/4 MILE EAST

2 WATER WELL OWNER: JUSTIN VYN
 RR#, St. Address, Box # : PO BOX 1227 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : SYRACUSE, KS 67878-1227 Application Number: 896

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 515 | ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 295 ft. below land surface measured on mo/day/yr 12/07/06
 Pump test data: Well water was 380 ft. after 4 hours pumping 689 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 515 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 515 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 350 ft. to 510 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 515 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHEAST How many feet? 265

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	25	04 SANDY CLAY			
25	43	05 SAND			
43	108	04 SANDY CLAY 05 SAND 20 LIMESTONE			
108	176	05 SAND 01 CLAY			
176	184	04 SANDY CLAY			
184	233	05 SAND 13 FINE GRAVEL 01 CLAY			
233	239	04 SANDY CLAY			
239	250	05 SAND 01 CLAY			
250	286	31 CALICHE 23 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/12/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/03/07 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 038 HAMILTON | SE 1/4 SW 1/4 SW 1/4 | 25 | T 25 S | R 43 W

2 WATER WELL OWNER: JUSTIN VYN
RR#, St. Address, Box # : PO BOX 1227 Board of Agriculture, Division of Water Resources
City, State, ZIP code : SYRACUSE, KS 67878-1227 Application Number: 896

FROM	TO	LITHOLOGIC LOG
286	321	23 SANDSTONE 31 CALICHE
321	332	31 CALICHE 23 SANDSTONE
332	364	23 SANDSTONE 31 CALICHE
364	386	23 SANDSTONE
386	394	23 SANDSTONE 28 ROCK
394	417	31 CALICHE 23 SANDSTONE
417	510	23 SANDSTONE
510	520	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/12/06 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/03/07
under the business name of HENKLE DRILLING & SUPPLY by (signature)

