

158

✓ ☆
Reno County SE NE sec. 21 25S. 1 7W Reno 12-2-57
50' N. of N. end of existing bridge (North Fork Minnescah River)
test hole

40

Elev. 0.4 ft. below bridge floor

Fill:

Silt and clay; contains much shale 4 4

Alluvium:

Silt, dark gray, sandy 0.5 4.5

Sand, silty, medium to fine 4.5 9

Sand, fine to coarse, grades
downward to gravel, fine to medium
and sand 4 13

Gravel, medium to fine and sand 20 33

Gravel, medium to fine, sand, and
silt, gray-green 3.1 36.1

Permian:

Shale, red, hard 3.9 40