

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

47,922

1 LOCATION OF WATER WELL: County: Reno		Fraction NE ¼ NE ¼ NW ¼ SE ¼		Section Number 34		Township No. T 25 S		Range Number R 7 ☐ E ☒ W																																																																			
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ From Partridge South to Parallel Rd. 1 mile E.				Global Positioning System (GPS) information: Latitude: 37.8319789 (in decimal degrees) Longitude: 98.0735096 (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☒ NAD 27 Collection Method: ☐ GPS unit (Make/Model: Garmin CXS) ☐ Digital Map/Photo, ☒ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																							
2 WATER WELL OWNER: David Krehbiel RR#, Street Address, Box #: 220 North Luka St. City, State, ZIP Code : Pratt, Kansas 67124																																																																											
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W E S ----- mile -----		4 DEPTH OF COMPLETED WELL 48 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL 16 ft. below land surface measured on mo/day/yr. 10-11-12..... Pump test data: Well water was.....ft. after..... hours pumping..... gpm EST. YIELD.....gpm. Well water was.....ft. after..... hours pumping..... gpm Bore Hole Diameter 40 in. to 48 ft., andin. toft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☒ Yes ☐ No																																																																									
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☐ Glued ☐ Clamped ☐ Welded ☐ Threaded Bolted Casing diameter 16 in. to 33 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface 24 in., Weight SCH 40 lbs./ft., Wall thickness or gauge No. 500 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☒ Stainless Steel ☐ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☒ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 33 ft. to 48 ft., From ft. to ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From 48 ft. to 26 ft., From ft. to ft. From ft. to ft., From ft. to ft.																																																																											
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From 26 ft. to 0 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well None Direction from well Distance from well																																																																											
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="width:10%;">FROM</th> <th style="width:10%;">TO</th> <th style="width:40%;">LITHOLOGIC LOG</th> <th style="width:10%;">FROM</th> <th style="width:10%;">TO</th> <th style="width:20%;">LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>4</td> <td>Sandy top soil</td> <td></td> <td></td> <td></td> </tr> <tr> <td>4</td> <td>7</td> <td>Tan clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>7</td> <td>47</td> <td>Small to fine sand</td> <td></td> <td></td> <td></td> </tr> <tr> <td>47</td> <td>48</td> <td>Red shale</td> <td></td> <td></td> <td></td> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	4	Sandy top soil				4	7	Tan clay				7	47	Small to fine sand				47	48	Red shale																																							
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																						
0	4	Sandy top soil																																																																									
4	7	Tan clay																																																																									
7	47	Small to fine sand																																																																									
47	48	Red shale																																																																									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 10-11-2012 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134 This Water Well Record was completed on (mo/day/year) 12-12-2012 under the business name of Rosencrantz-Bemis Enterprise by (signature) Danielle A. Odom																																																																											
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																											