

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

47,575

1 LOCATION OF WATER WELL: County: Reno		Fraction NE ¼ NE ¼ SE ¼ NE ¼		Section Number 19		Township No. T 25 S		Range Number R 9 ☐ E ☒ W					
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ From Fairfield School-1 mile W, 1/4S, WSR				Global Positioning System (GPS) information: Latitude: 37.86433 (in decimal degrees) Longitude: 098.34331 (in decimal degrees) Elevation: 1708 Datum: ☐ WGS 84, ☐ NAD 83, ☒ NAD 27 Collection Method: ☒ GPS unit (Make/Model: Garmin csx) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☒ 5-15 m, ☐ >15 m									
2 WATER WELL OWNER: Larry Preisser RR#, Street Address, Box #: 105 S.E. 130th Avenue City, State, ZIP Code : Cunningham, Kansas 67035													
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="width:100%; text-align: center; border-collapse: collapse;"> <tr> <td style="width:50%;">NW</td> <td style="width:50%;">NE</td> </tr> <tr> <td>SW</td> <td>SE</td> </tr> </table> S [-----1 mile-----]		NW	NE	SW	SE	4 DEPTH OF COMPLETED WELL 67 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL 16 ft. below land surface measured on mo/day/yr. 3-15-2011 Pump test data: Well water was..... ft. after..... hours pumping..... gpm EST. YIELD..... gpm. Well water was..... ft. after..... hours pumping..... gpm Bore Hole Diameter 40 in. to 67 ft., and..... in. to..... ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☒ Yes ☐ No							
NW	NE												
SW	SE												
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other..... CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 16 in. to 47 ft., Diameter..... in. to..... ft., Diameter..... in. to..... ft. Casing height above land surface 20 in., Weight SCH 40 lbs./ft., Wall thickness or gauge No. 500 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify)..... ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify)..... SCREEN-PERFORATED INTERVALS: From 47 ft. to 67 ft., From..... ft. to..... ft. GRAVEL PACK INTERVALS: From 67 ft. to 20 ft., From..... ft. to..... ft. From..... ft. to..... ft., From..... ft. to..... ft.													
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other..... Grout Intervals: From 20 ft. to 3 ft., From..... ft. to..... ft., From..... ft. to..... ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well none Direction from well..... Distance from well.....													
FROM	TO	LITHOLOGIC LOG		FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS							
0	2	Top soil											
2	7	Tan clay silty											
7	39	Small to medium sand											
39	42	Tan clay											
42	50	Small to fine sand											
50	55	Small to medium sand											
55	58	Sm. to med. sand w/tan clay 50/50											
58	66	Small sand											
66	67	Red bed											
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 3-15-2011 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134 This Water Well Record was completed on (mo/day/year) 3-17-2011 under the business name of Rosencrantz-Bemis Ent. by (signature) <i>James Dadeau</i>													
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .													