

1 LOCATION OF WATER WELL: Sedgwick	FRACTION SE 1/4 NE 1/4 SE 1/4	Section Number 4	Township Number T 26 S	Range Number R 1W E/W
--	---	----------------------------	----------------------------------	---------------------------------

Distance and direction from nearest town or city street address of well if located within city?

2 miles East & 2 1/4 miles North of Maize, Kansas

WATER WELL OWNER: WIRTH, Keith	Board of Agriculture, Division of Water Resource
RR#, ST. ADDRESS, BOX #: 829 W. 35th North	
CITY, STATE, ZIP CODE: Wichita, Kansas 67204	Application Number: 43,549

LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 	4 DEPTH OF COMPLETED WELL 127 ft. ELEVATION:
	Depth(s) groundwater Encountered 1 ft. 2 ft. 3 ft.
	WELL'S STATIC WATER LEVEL 9 FT. BELOW LAND SURFACE MEASURED ON mo/day/yr 03/29/1999
	Pump test data: Well water was ft. after hours pumping gpm
	Est. Yield gpm : Well water was ft. after hours pumping gpm
Bore Hole Diameter 30 in. to 127 ft. and in. to ft.	
WELL WATER TO BE USED AS:	
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)	
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well	
Was a chemical/bacteriological sample submitted to Department? Yes submitted	No X ; If yes, mo/day/yr sample was Water Well Disinfected? Yes X No

5 TYPE OF CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS:
1 Steel 3 RMP (SR)	6 Asbestos-Cement	9 Other (Specify below)	Glued X Clamped
2 PVC 4 ABS	7 Fiberglass	SDR-26	Welded
Blank casing Diameter 16 in. to 87 ft., Dia in. to ft., Dia in. to ft.			Threaded
Casing height above land surface 12 in., weight 19.750 lbs. / ft.			Wall thickness or gauge No. .616
TYPE OF SCREEN OR PERFORATION MATERIAL:	5 Fiberglass	8 RMP (SR)	10 Asbestos-cement
1 Steel 3 Stainless Steel	6 Concrete tile	9 ABS	11 other (specify)
2 Brass 4 Galvanized steel			12 None used (open hole)
SCREEN OR PERFORATION OPENING ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continous slot 3 Mill slot	6 Wire wrapped	9 Drilled holes	
2 Louvered shutter 4 Key punched	7 Torch cut	10 Other (specify)	
SCREEN-PERFORATION INTERVALS:	from 87 ft. to 127 ft., From ft. to ft.		
GRAVEL PACK INTERVALS:	from 20 ft. to 127 ft., From ft. to ft.		

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other bentonite hole plug
Grout Intervals: From 0 ft. to 20 ft. From ft. to ft.				
What is the nearest source of possible contamination:	10 Livestock pens	14 Abandon water well		
1 Septic tank 4 Lateral lines 7 Pit privy	11 Fuel storage	15 Oil well/Gas well		
2 Sewer lines 5 Cess pool 8 Sewage lagoon	12 Fertilizer storage	16 Other (specify below)		
3 Watertight sewer lines 6 Seepage pit 9 Feedyard	13 Insecticide storage	None Apparent		

Direction from well?			How many feet?		
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5	sandy soil			
5	25	fine to medium sand			
25	40	medium to coarse sand			
40	59	gray clay			
59	65	tan clay			
65	92	fine to coarse sand & fine gravel w/ clay streaks			
92	107	tan clay			
107	125	fine to coarse sand and fine gravel			
125	127	gray clay			

RECEIVED**MAY 11 1999****BUREAU OF WATER**

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 03/29/1999 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This Water Well Record was completed on (mo/day/yr) 03/31/99 Under the business name of Harp Well & Pump Service, Inc. by (signature)
--

Todd S. Harp