

5073

WATER WELL RECORD Form WWC-5 KSA 82a-1212 ID No. TW 5-00

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
County: Sedgwick		SW ¼ SW ¼ NW ¼		31		T 26 S		R 1 EW	
Distance and direction from nearest town or city street address of well if located within city? Approximately 1½ miles south and 1 mile west of Maize									
2 WATER WELL OWNER: City of Maize									
RR#, St. Address, Box #: P.O. Box 245									
City, State, ZIP Code: Maize, KS 67101									
Board of Agriculture, Division of Water Resources Application Number:									
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:			4 DEPTH OF COMPLETED WELL: 172 ft. ELEVATION: unknown						
			Depth(s) Groundwater Encountered 1. 19.22 ft. below land surface measured on mo/day/yr 6-7-00						
			WELL'S STATIC WATER LEVEL: 19.22 ft. below land surface measured on mo/day/yr 6-7-00						
			Pump test data: Well water was not ch'd ft. after hours pumping gpm						
			Est. Yield unknown gpm: Well water was ft. after hours pumping gpm						
			Bore Hole Diameter: 9 in. to 180 ft., and in. to ft.						
WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well									
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)									
2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Test Well									
Was a chemical/bacteriological sample submitted to Department? Yes. No. X; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No X									
5 TYPE OF BLANK CASING USED:									
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued. X Clamped.									
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded									
7 Fiberglass Threaded.									
Blank casing diameter 5 in. to 105 ft., Dia 5 in. to 150 ft., Dia in. to ft.									
Casing height above land surface 24 in., weight 2.36 lbs./ft. Wall thickness or gauge No. .214									
TYPE OF SCREEN OR PERFORATION MATERIAL:									
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 8 RMP (SR) 10 Asbestos-cement									
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify)									
12 None used (open hole)									
SCREEN OR PERFORATION OPENINGS ARE:									
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)									
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes									
7 Torch cut 10 Other (specify) ft.									
SCREEN-PERFORATED INTERVALS: From 105 ft. to 125 ft., From ft. to ft.									
From 150 ft. to 170 ft., From ft. to ft.									
GRAVEL PACK INTERVALS: From 95 ft. to 180 ft., From ft. to ft.									
From ft. to ft., From ft. to ft.									
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Bentonite Holeplug									
Grout Intervals: From 25 ft. to 75 ft., From 0 ft. to 25 ft., From 75 ft. to 95 ft.									
What is the nearest source of possible contamination:									
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well									
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well									
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)									
13 Insecticide storage None known									
Direction from well? How many feet?									
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS				
0	2	Topsoil							
2	9	Clay, dark gray							
9	16	Clay, brown, sandy							
16	64	Sand and gravel, medium, fine							
64	67	Clay, tan and gray							
67	78	Sand and gravel, medium, fine							
78	95	Clay, gray, green							
95	129	Sand and gravel, medium, fine							
129	143	Clay, gray, green							
143	171	Sand and gravel, medium, fine							
171	175	Clay, reddish brown							
175	179	Sand and gravel, medium, fine							
179	180	Cemented sand							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6-7-00 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's Licence No. 185 This Water Well Record was completed on (mo/day/yr) 6-14-00 under the business name of Clarke Well & Equipment, Inc. by (signature)									
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone 785-296-5524. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.									