

LOCATION OF WATER WELL:		FRACTION	SECTION NUMBER	TOWNSHIP NUMBER	RANGE NUMBER
Sedgwick		NE 1/4 SW 1/4 SE 1/4	32	T 26 S	R 1W E/W
Distance and direction from nearest town or city street address of well if located within city?					
3128 Den Hollow Wichita, Kansas					
WATER WELL OWNER:		RKC HOMES			
RR#,ST. ADDRESS,BOX #:		12528 W. Central Board of Agriculture, Division of Water Resource			
CITY, STATE:		Wichita, Kansas		ZIP CODE: Application Number:	
LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: A square divided into four smaller squares labeled NW, NE, SW, and SE. An 'X' is drawn in the center of the SE square.		DEPTH OF COMPLETED WELL: 85 ft. ELEVATION:			
		Depth of groundwater Encountered: ft.			
		WELL'S STATIC WATER LEVEL 20 FT. BELOW LAND SURFACE MEASURED ON mo/day/yr: 3/10/05			
		Pump test data: Well water was ft. after hours of pumping @ gpm			
		Est. Yield: gpm Well water was ft. after hours of pumping @ gpm			
		Bore Hole Diameter 12 in. to 85 ft. and in. to ft.			
		WELL WATER TO BE USED AS:			
		1. Domestic 3. Feedlot 5. Public water supply 7. Lawn and garden only 9. Dewatering 11. Injection well 2. Irrigation 4. Industrial 6. Oil field water supply 8. Air conditioning 10. Monitoring well 12. Other (Specify below)			
		Was a chemical/bacteriological sample submitted to Department? YES NO ; If yes, what mo/day/yr was sample submitted Was Water Well Disinfected? YES NO			
TYPE OF CASING USED:		CASING JOINTS: Glued Threaded Welded Clamped			
Blank casing diameter 5 in. to 65 ft., Dia. in. to ft., Dia. in. to ft.		SDR-26			
Casing height above land surface: 24 in., Weight: 2.35 lbs./ft. Wall thickness or gauge No. .214					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
SCREEN OR PERFORATION OPENINGS ARE:					
SCREEN - PERFORATION INTERVAL From 65 ft. to 85 ft., From ft. to ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 24 ft. to 85 ft., From ft. to ft., From ft. to ft.					
GROUT MATERIALS:		Other bentonite hole plug			
Grout Intervals: From 4 ft. to 24 ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:					
Direction from well? North How many feet? 50 ft. plus					
From To LITHOLOGIC LOG		From To LITHOLOGIC LOG			
0	4	topsoil			
4	35	sandy clay			
35	60	sand with clay streaks			
60	84	medium coarse sand			
84	85	clay			
Contractor's or Landowner's Certification: This water well was 1. constructed 2. reconstructed or 3. plugged under my jurisdiction and was completed on (mo/day/year) 3/10/2005 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 235 This water well record was completed on (mo/day/year) 3/11/2005 under the business name of HARP Well and Pump Service by (signature) Jedd S. Harper					