

1 LOCATION OF WATER WELL: Sedgwick	FRACTION SE 1/4 NW 1/4 SE 1/4	SECTION NUMBER 30	TOWNSHIP NUMBER T 26 S	RANGE NUMBER R 1W E/W
--	----------------------------------	-----------------------------	---------------------------	--------------------------

Distance and direction from nearest town or city street address of well if located within city?
10706 Havenhurst Wichita, Kansas

2 WATER WELL OWNER:	ROBL CONSTRUCTION			Board of Agriculture, Division of Water Resource
RR#, ST. ADDRESS, BOX #:	5842 W. 21st N.			
CITY, STATE:	Wichita, Kansas	ZIP CODE:		

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL: **62** ft.
 Depth of groundwater Encountered: _____ ft.
 WELL'S STATIC WATER LEVEL **25** FT. BELOW LAND SURFACE MEASURED ON **mo/day/yr: 4/4/07**
 Pump test data: Well water was _____ ft. after _____ hours of pumping @ _____ gpm
 Est. Yield: _____ gpm Well water was _____ ft. after _____ hours of pumping @ _____ gpm
 Bore Hole Diameter **12** in. to **62** ft. and _____ in. to _____ ft.
 WELL WATER TO BE USED AS:
☐ Domestic ☒ Feedlot ☐ Public water supply ☒ Lawn and garden only ☐ Dewatering ☐ Injection well
☐ Irrigation ☐ Industrial ☐ Oil field water supply ☐ Air conditioning ☐ Monitoring well
 Was a chemical/bacteriological sample submitted to Department? YES NO ; If yes, what mo/day/yr was sample submitted
 Was Water Well Disinfected? YES NO

5 TYPE OF CASING USED:
☐ Steel ☒ RPM (SR) ☐ Wrought Iron ☐ Fiberglass ☐ Other (Specify below)
☒ PVC ☐ ABS ☐ Asbestos-Cement ☐ Concrete tile **SDR-26**
 Blank casing diameter **5** in. to **42** ft., Dia. _____ in. to _____ ft., Dia. _____ in. to _____ ft.
 Casing height above land surface: **12** in., Weight: **2.35** lbs. / ft. Wall thickness or gauge No. **.214**
 TYPE OF SCREEN OR PERFORATION MATERIAL:
☐ Steel ☐ Stainless Steel ☐ Fiberglass ☒ PVC ☐ ABS
☐ Brass ☐ Galvanized ☐ Concrete Tile ☐ RMP (SR) ☐ Asbestos-Cement ☐ None used (open hole)

CASING JOINTS: ☒ Glued Threaded
 Welded Clamped
 SCREEN OR PERFORATION OPENINGS ARE:
☐ Continuous slot ☐ Mill slot ☐ Gauzed wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole)
☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify)

SCREEN - PERFORATION INTERVAL From **42** ft. to **62** ft., From ____ ft. to ____ ft., From ____ ft. to ____ ft.
 GRAVEL PACK INTERVALS: From **24** ft. to **62** ft., From ____ ft. to ____ ft., From ____ ft. to ____ ft.

6 GROUT MATERIALS: 1. Neat cement 2. Cement Grout 3. Bentonite Other bentonite hole plug
 Grout Intervals: From **4** ft. to **24** ft., From ____ ft. to ____ ft., From ____ ft. to ____ ft.
 What is the nearest source of possible contamination:
☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Oil well/Gas well
☐ Sewer lines ☐ Cess Pool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandon water well ☐ Other (specify below)
☒ Watertight sewer line ☐ Seepage pit ☐ Feed yard ☐ Fertilizer storage
 Direction from well? North How many feet? **15**

From	To	LITHOLOGIC LOG	From	To	LITHOLOGIC LOG
0	4	topsoil			
4	12	clay			
12	20	fine sand			
20	25	clay			
25	35	coarse sand			
35	38	clay			
38	62	medium sand			

Contractor's or Landowner's Certification: This water well was 1. constructed under my jurisdiction and was completed on (mo/day/year) **4-4-2007** and this record is true to the best of my knowledge and belief.
 Kansas Water Well Contractor's License No. **236**
 under the business name of **Harp Well and Pump Service** by (signature) **Todd S. Harp**

This water well record was completed on (mo/day/year) **4-9-2007**