

LOCATION OF WATER WELL: Sedgwick		FRACTION SW NW SE NE	SECTION NUMBER 33	TOWNSHIP NUMBER T S	RANGE NUMBER R E/W																																																																																																																		
Distance and direction from nearest town or city street address of well if located within city? 8302 W. Lang Wichita, Kansas 26																																																																																																																							
WATER WELL OWNER: RINDFUSS, Brad																																																																																																																							
RR#,ST. ADDRESS,BOX #: 8302 W. Lang Board of Agriculture, Division of Water Resource																																																																																																																							
CITY, STATE: Wichita, Kansas ZIP CODE: Application Number:																																																																																																																							
LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		DEPTH OF COMPLETED WELL: 65 ft. ELEVATION: Depth of groundwater Encountered: _____ ft. WELL'S STATIC WATER LEVEL 20 FT. BELOW LAND SURFACE MEASURED ON mo/day/yr: 4/24/07 Pump test data: Well water was _____ ft. after _____ hours of pumping @ _____ gpm Est. Yield: _____ gpm Well water was _____ ft. after _____ hours of pumping @ _____ gpm Bore Hole Diameter 12 in. to 65 ft. and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☐ Domestic ☒ Feedlot ☐ Public water supply ☒ Lawn and garden only ☐ Dewatering ☐ Injection well ☐ Irrigation ☐ Industrial ☐ Oil field water supply ☐ Air conditioning ☐ Monitoring well ☐ Other (Specify below) Was a chemical/bacteriological sample submitted to Department? YES NO ; If yes, what mo/day/yr was sample submitted Was Water Well Disinfected? YES NO																																																																																																																					
TYPE OF CASING USED: ☐ Steel ☐ RPM (SR) ☐ Wrought Iron ☐ Fiberglass ☐ Other (Specify below) CASING JOINTS: ☒ Glued Threaded ☒ PVC ☐ ABS ☐ Asbestos-Cement ☐ Concrete tile SDR-26 Welded Clamped Blank casing diameter 5 in. to 45 ft., Dia. _____ in. to _____ ft., Dia. _____ in. to _____ ft. Casing height above land surface: 12 in., Weight: 2.35 lbs./ft. Wall thickness or gauge No. .214 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☐ Fiberglass ☒ PVC ☐ ABS ☐ Other (specify) ☐ Brass ☐ Galvanized ☐ Concrete Tile ☐ RMP (SR) ☐ Asbestos-Cement ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauzed wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify) SCREEN - PERFORATION INTERVAL From 45 ft. to 65 ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 24 ft. to 65 ft., From _____ ft. to _____ ft.																																																																																																																							
GROUT MATERIALS: 1. Neat cement 2. Cement Grout 3. Bentonite Other bentonite hole plug Grout Intervals: From 4 ft. to 24 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Oil well/Gas well - ☐ Sewer lines ☐ Cess Pool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandon water well ☐ Other (specify below) ☒ Watertight sewer line ☐ Seepage pit ☐ Feed yard ☐ Fertilizer storage Direction from well? North How many feet? 25 ft. plus																																																																																																																							
<table border="1" style="width:100%;"> <thead> <tr> <th>From</th> <th>To</th> <th>LITHOLOGIC LOG</th> <th>From</th> <th>To</th> <th>LITHOLOGIC LOG</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>3</td> <td>topsoil</td> <td></td> <td></td> <td></td> </tr> <tr> <td>3</td> <td>23</td> <td>clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>23</td> <td>28</td> <td>clay and sand mix</td> <td></td> <td></td> <td></td> </tr> <tr> <td>28</td> <td>40</td> <td>fine sand</td> <td></td> <td></td> <td></td> </tr> <tr> <td>45</td> <td>65</td> <td>medium sand</td> <td></td> <td></td> <td></td> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>						From	To	LITHOLOGIC LOG	From	To	LITHOLOGIC LOG	0	3	topsoil				3	23	clay				23	28	clay and sand mix				28	40	fine sand				45	65	medium sand																																																																																	
From	To	LITHOLOGIC LOG	From	To	LITHOLOGIC LOG																																																																																																																		
0	3	topsoil																																																																																																																					
3	23	clay																																																																																																																					
23	28	clay and sand mix																																																																																																																					
28	40	fine sand																																																																																																																					
45	65	medium sand																																																																																																																					
Contractor's or Landowner's Certification: This water well was 1. constructed or 2. reconstructed or 3. plugged under my jurisdiction and was completed on (mo/day/year) 4-24-2007 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This water well record was completed on (mo/day/year) 4-27-2007 under the business name of Harp Well and Pump Service by (signature) Todd S. Harp																																																																																																																							