

1 LOCATION OF WATER WELL: Sedgwick		FRACTION SE 1/4 SE 1/4 NW 1/4		SECTION NUMBER 12		TOWNSHIP NUMBER T 26 S		RANGE NUMBER R 1W E/W	
Distance and direction from nearest town or city street address of well if located within city? 6654 N. Sheridan Wichita, Kansas									
2 WATER WELL OWNER: RR#,ST. ADDRESS,BOX #: CITY, STATE:		ROYSE, C. 6654 N. Sheridan Wichita, Kansas				Board of Agriculture, Division of Water Resource Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: 50 ft. ELEVATION: Depth of groundwater Encountered: ft. WELL'S STATIC WATER LEVEL 15 FT. BELOW LAND SURFACE MEASURED ON 11/1/07 Pump test data: Well water was ft. after hours of pumping @ gpm Est. Yield: gpm Well water was ft. after hours of pumping @ gpm Bore Hole Diameter 12 in. to 50 ft. and in. to ft. WELL WATER TO BE USED AS: ☒ 1. Domestic ☐ 3. Feedlot ☐ 5. Public water supply ☐ 7. Lawn and garden only ☐ 9. Dewatering ☐ 11. Injection well ☐ 2. Irrigation ☐ 4. Industrial ☐ 6. Oil field water supply ☐ 8. Air conditioning ☐ 10. Monitoring well Was a chemical/bacteriological sample submitted to Department? YES ☒ NO ; If yes, what mo/day/yr was sample submitted Was Water Well Disinfected? ☒ YES ☐ NO							
5 TYPE OF CASING USED: ☒ 1. Steel ☐ 3. RPM (SR) ☐ 5. Wrought Iron ☐ 7. Fiberglass ☐ 9. Other (Specify below) ☒ 2. PVC ☐ 4. ABS ☐ 6. Asbestos-Cement ☐ 8. Concrete tile SDR-26 Blank casing diameter 5 in. to 40 ft., Dia. in. to ft., Dia. in. to ft. Casing height above land surface: 12 in., Weight: 2.35 lbs. / ft. Wall thickness or gauge No. .214 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ 1. Steel ☐ 3. Stainless Steel ☐ 5. Fiberglass ☒ 7. PVC ☐ 9. ABS ☐ 11. Other (specify) ☐ 2. Brass ☐ 4. Galvanized ☐ 6. Concrete Tile ☐ 8. RMP (SR) ☐ 10. Asbestos-Cement ☐ 12. None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ 1. Continuous slot ☐ 3. Mill slot ☐ 5. Gauzed wrapped ☐ 7. Torch cut ☐ 9. Drilled holes ☐ 11. None (open hole) ☐ 2. Louvered shutter ☐ 4. Key punched ☐ 6. Wire wrapped ☒ 8. Saw cut ☐ 10. Other (specify) SCREEN - PERFORATION INTERVAL From 40 ft. to 50 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 24 ft. to 50 ft., From ft. to ft. From ft. to ft., From ft. to ft.									
6 GROUT MATERIALS: Grout Intervals: From 4 ft. to 24 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ 1. Septic tank ☐ 4. Lateral lines ☐ 7. Pit privy ☐ 10. Livestock pens ☐ 13. Insecticide storage ☐ 15. Oil well/Gas well ☐ 2. Sewer lines ☐ 5. Cess Pool ☐ 8. Sewage lagoon ☐ 11. Fuel storage ☐ 14. Abandon water well ☐ 16. Other (specify below) ☐ 3. Watertight sewer line ☐ 6. Seepage pit ☐ 9. Feed yard ☐ 12. Fertilizer storage None Apparent Direction from well? How many feet?									
From To LITHOLOGIC LOG From To LITHOLOGIC LOG 0 2 sandy soil 2 15 clay 15 33 coarse sand 33 38 clay 38 50 coarse sand									
7 Contractor's or Landowner's Certification: This water well was ☒ constructed ☐ reconstructed or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 11/01/2007 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This water well record was completed on (mo/day/year) 11/9/2007 under the business name of Harp Well and Pump Service by (signature) Todd S. Harp									