

WATER WELL RECORD Form WWC-5


☒ Original Record ☐ Correction ☐ Change in Well Use

Division of Water
Resources App. No.

Well ID

1 LOCATION OF WATER WELL: County: <u>Sedgwick</u>		Fraction <u>1/4 NW 1/4 SE 1/4 SW 1/4</u>	Section Number <u>32</u>	Township Number <u>T 26 S</u>	Range Number <u>R 1 E 1 W</u>
---	--	---	-----------------------------	----------------------------------	----------------------------------

2 WELL OWNER: Last Name: <u>Chapman Custom Homes LLC</u> Business: <u>PO Box 9491</u> Address: <u>Wichita</u> City: <u>Wichita</u> State: <u>KS</u> ZIP: <u>67277</u>		Street or Rural Address where well is located (if unknown, distance and direction from nearest town or intersection): If at owner's address, check here: ☐ <u>9817 W Westlakes Ct</u> <u>Wichita, KS 67205</u>
---	--	---

3 LOCATE WELL WITH "X" IN SECTION BOX: 	4 DEPTH OF COMPLETED WELL: <u>69</u> ft. Depth(s) Groundwater Encountered: 1) <u>11</u> ft. 2) <u>46</u> ft. 3) ft., or 4) ☐ Dry Well WELL'S STATIC WATER LEVEL: <u>46</u> ft. ☒ below land surface, measured on (mo-day-yr) <u>10-23-13</u> ☐ above land surface, measured on (mo-day-yr) Pump test data: Well water was ft. after hours pumping gpm Well water was ft. after hours pumping gpm Estimated Yield: <u>25</u> gpm Bore Hole Diameter: <u>12</u> in. to <u>69</u> ft. and in. to ft.	5 Latitude: (decimal degrees) Longitude: (decimal degrees) Datum: ☐ WGS 84 ☐ NAD 83 ☐ NAD 27 Source for Latitude/Longitude: ☐ GPS (unit make/model:) (WAAS enabled? ☐ Yes ☐ No) ☐ Land Survey ☐ Topographic Map ☐ Online Mapper:
	6 Elevation: ft. ☐ Ground Level ☐ TOC Source: ☐ Land Survey ☐ GPS ☐ Topographic Map ☐ Other	

7 WELL WATER TO BE USED AS:

1. Domestic: ☐ Household ☒ Lawn & Garden ☐ Livestock	2. ☐ Irrigation	3. ☐ Feedlot	4. ☐ Industrial	5. ☐ Public Water Supply: well ID	6. ☐ Dewatering: how many wells?	7. ☐ Aquifer Recharge: well ID	8. ☐ Monitoring: well ID	9. Environmental Remediation: well ID ☐ Air Sparge ☐ Soil Vapor Extraction ☐ Recovery ☐ Injection	10. ☐ Oil Field Water Supply: lease	11. Test Hole: well ID ☐ Cased ☐ Uncased ☐ Geotechnical	12. Geothermal: how many bores? a) Closed Loop ☐ Horizontal ☐ Vertical b) Open Loop ☐ Surface Discharge ☐ Inj. of Water	13. ☐ Other (specify):
---	--	-------------------------------------	--	--	---	---	---	---	--	---	---	---

Was a chemical/bacteriological sample submitted to KDHE? ☐ Yes ☒ No If yes, date sample was submitted:
 Water well disinfected? ☒ Yes ☐ No

8 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other **CASING JOINTS:** ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded
 Casing diameter 5 in. to ft., Diameter in. to ft., Diameter in. to ft.
 Casing height above land surface 12 in. Weight 24 lbs./ft. Wall thickness or gauge No. 160psi
TYPE OF SCREEN OR PERFORATION MATERIAL:
☐ Steel ☐ Stainless Steel ☐ Fiberglass ☒ PVC ☐ Other (Specify)
☐ Brass ☐ Galvanized Steel ☐ Concrete tile ☐ None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:
☐ Continuous Slot ☒ Mill Slot ☐ Gauze Wrapped ☐ Torch Cut ☐ Drilled Holes ☐ Other (Specify)
☐ Louvered Shutter ☐ Key Punched ☐ Wire Wrapped ☐ Saw Cut ☐ None (Open Hole)
SCREEN-PERFORATED INTERVALS: From 69 ft. to 57 ft., From ft. to ft., From ft. to ft.
GRAVEL PACK INTERVALS: From 69 ft. to 40 ft., From ft. to ft., From ft. to ft.

9 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other
 Grout Intervals: From 40 ft. to 3 ft., From ft. to ft., From ft. to ft.

Nearest source of possible contamination:
☐ Septic Tank ☐ Lateral Lines ☐ Pit Privy ☐ Livestock Pens ☐ Insecticide Storage
☒ Sewer Lines ☐ Cess Pool ☐ Sewage Lagoon ☐ Fuel Storage ☐ Abandoned Water Well
☐ Watertight Sewer Lines ☐ Seepage Pit ☐ Feedyard ☐ Fertilizer Storage ☐ Oil Well/Gas Well
☐ Other (Specify)
 Direction from well? S Distance from well? 20' ft.

10 FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	1	top soil			
1	11	clay			
11	33	fine sand			
33	38	med sand			
38	39	clay			
39	56	fine sand			
56	63	med Gravel			
63	69	med Sand			

Notes:

11 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo-day-year) 10-23-13 and this record is true to the best of my knowledge and belief.
 Kansas Water Well Contractor's License No. 10740 This Water Well Record was completed on (mo-day-year) 11-22-13 under the business name of Wenger Drilling

INSTRUCTIONS: Send one copy to WATER WELL OWNER and retain one copy for your records. Submit fee of \$5.00 for each constructed well along with one (white) copy to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone (785) 296-3565.