

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 SE 1/4 NW 1/4	Section number 18	Township number T 26 S R 1	Range number 1
2. Distance and direction from nearest town or city: 1/2 mile West of Maize, Kansas				3. Owner of well: Leo Wetta R.R. or street: Maize, Kansas City, state, zip code:		
4. Locate with "X" in section below: Sketch map: Well No. 1				6. Bore hole dia. 30 in. Completion date 3/11/77 Well depth 55 ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material Stl Height: Above ground 12 in. Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 21.75 lbs./ft. Dia. 16 in. to 24 ft. depth Wall Thickness: inches or Dia. 16 in. to 24 ft. depth gage No. 188		
5. Type and color of material		From	To	10. Screen: Manufacturer's name Doerr Metal Products Type Steel Dia. 16" Slot/gauze 1/8" Length 32' Set between 23 ft. and 55 ft. ft. and 55 ft. Gravel pack? yes Size range of material 1/4 x 1/2		
Soil		0	3	11. Static water level: 7.0 ft. below land surface Date 12/15/76 mo./day/yr.		
Clay		3	5	12. Pumping level below land surfaces: No Test ft. after 0 hrs. pumping 0 g.p.m. ft. after 0 hrs. pumping 0 g.p.m. Estimated maximum yield 600 g.p.m.		
Fine sand		5	7	13. Water sample submitted: Yes ☒ No ☐ Date 12/15/76 mo./day/yr.		
Med. to coarse sand & gravel		7	23	14. Well head completion: 12 inches above grade ☐ Pitless adapter ☒ Pitless adapter		
Green clay w/sand & gravel		23	25	15. Well grouted? Yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
Med. to coarse sand & gravel		25	55	16. Nearest source of possible contamination: ft. 1350 Direction West Type Form Well disinfected upon completion? ☐ Yes ☒ No		
				17. Pump: ☐ Not installed Manufacturer's name Layne - Wellline Model number 10KH-EM HP 25 Volts 440 Length of drop pipe 40 ft. capacity 500 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name Wichita Kansas License No. Address Wichita Kansas Signed [Signature] Date 3-21-77 Authorized representative		
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						

26 - 18 NW SE NW
 1/4 1/4 1/4 1/4
 Sec 18

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5