


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 820-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County SEDGWICK	Fraction SW 1/4 NE NE	Section number 19	Township number T 26 S	Range number R 1 W E/W
2. Distance and direction from nearest town or city:			3. Owner of well: W.B. BERTRAM			
Street address of well location if in city: 115 EAST ALBERT MAIZE, KANSAS			R.R. or street: 1226 BAKER City, state, zip code: WICHITA, KANS-67212			
4. Locate with "X" in section below:		Sketch map: BORED 10" HOLE TO 16' (H2O) - INSTALLED 6" CASING - USED SAND BUCKET TO COMPLETE AT 36' GROUTED TO STATIC - 16'		6. Bore hole dia. 10 in. Completion date 12-15-78 Well depth 36 ft. GRADE		
				7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☒ Reverse rotary ☐		
5. Type and color of material		From To		8. Use: Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Coin ☒ Laundry ☒ Lawn ☐ Oil field water ☒ Other ☐		
TOP SOIL - BLACK		0 2.5		9. Casing: Material EMP Height: Above or below 0 Threaded 5/8 Welded ☒ Surface 1 1/2 in. RMP ☒ PVC ☐ Weight 240 lbs./ft. Dia. 6 in. to 36 ft. depth Wall Thickness: inches or 0.070 Dia. 6 in. to 36 ft. depth Gage No. 10207		
SANDY CLAY BLACK		2.5 7		10. Screen: Manufacturer's name SUNFLOWER Type PLASTIC Dia. 6 in. 1 1/2 Slot/gauze 0.31 Length 9 ft. Set between 97 ft. and 36 ft. ft. and ft.		
CLAY BROWN		7 12		Gravel pack? NA Size range of material		
CLAY - RED		12 14		11. Static water level: 16 ft. below land surface Date 12-15-78		
CLAY - SANDY - YELLOWISH		14 16.5		12. Pumping level below land surfaces: ft. after hrs. pumping NA g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 100 g.p.m.		
GRAVEL - BROWN - VERY LARGE		16.5 18		13. Water sample submitted: NO Date		
GRAVEL - BROWN - LARGE		18 23		14. Well head completion: 12 inches above grade Pitless adapter 12 inches above grade		
SAND - TAN - COARSE		23 36		15. Well grouted? YES With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 16 ft.		
				16. Nearest source of possible contamination: ft. 10 Direction N Type CAST IRON Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump: ☒ Not installed Manufacturer's name Model number HP Volts Length of drop pipe ft. capacity g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation: 1300'		19. Remarks: THIS WELL CRED BY DWIGHT BRINKLEY - OWNER SIGNED STATEMENT WATER WILL NOT BE USED FOR DRINKING - SPECIAL GROUT DEPTH BECAUSE CUST. THOUGHT SEWER WAS CLAY - LATER (AFTER DRILLING) SAID HE'S SURE SEWER IS CAST IRON - WILL BE USED FOR COIN LAUNDRY + TOILET. W.B.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. BEARDEN PUMPWELL Business name License No. Address 3142 MENTOR WICHITA, KANSAS Signed Chil Barden Date 1-3-79 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5