

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Sedgwick</u>	Fraction <u>NW 1/4 SE 1/4</u>	Section number <u>19</u>	Township number T <u>24</u> S R	Range number <u>1 W E</u>
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>726 Queen</u>				3. Owner of well: <u>Troy Griffin Construction Co</u> R.R. or street: <u>702 JAMES</u> City, state, zip code: <u>MAIZE KS 67101</u>		
4. Locate with "X" in section below: Sketch map: N 1 Mile W E S 1 Mile				6. Bore hole dia. <u>9</u> in. Completion date Well depth <u>44</u> ft. <u>7-7-79</u>		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☐ Reverse rotary		
				8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
				9. Casing: Material <u>RMP</u> Height: Above or below Threaded ☐ Welded <u>GLD</u> Surface <u>12</u> in. RMP ☒ PVC ☐ Weight <u>19.5</u> lbs./ft. Dia. <u>4</u> in. to <u>9</u> ft. depth Wall Thickness: inches or Dia. <u>4</u> in. to <u>44</u> ft. depth gage No. <u>20</u>		
5. Type and color of material				From	To	10. Screen: Manufacturer's name <u>Sunflower</u>
<u>Reddish Sandy clay</u>				<u>0</u>	<u>8</u>	Type <u>RMP</u> Dia. <u>4</u> "
<u>Yellow/Orange Iron oxide (Rust)</u>				<u>8</u>	<u>10</u>	Slot/gauze <u>3/16</u> Length <u>5</u> ft
<u>LT. Brown med. fine sand</u>				<u>10</u>	<u>28</u>	Set between <u>39</u> ft. and <u>44</u> ft.
<u>" " med coarse sand</u>				<u>28</u>	<u>40</u>	Gravel pack? <u>No</u> Size range of material
<u>" " " " gravel</u>				<u>40</u>	<u>44</u>	11. Static water level: mo./day/yr. <u>28</u> ft. below land surface Date <u>7-7-79</u>
						12. Pumping level below land surfaces: ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield <u>260</u> g.p.m.
						13. Water sample submitted: mo./day/yr. ____ Yes ☒ No Date
						14. Well head completion: ____ Pitless adapter <u>12</u> Inches above grade
						15. Well grouted? <u>No</u> <u>CK</u> Remarks <u>*</u> With: ____ Neat cement ____ Bentonite ____ Concrete Depth: From ____ ft. to ____ ft.
						16. Nearest source of possible contamination: ft. <u>15</u> Direction <u>South</u> Type <u>Plastic Sewer</u> Well disinfected upon completion? ____ Yes ☒ No
						17. Pump: ☒ Not installed Manufacturer's name Model number ____ HP ____ Volts ____ Length of drop pipe ____ ft. capacity ____ g.p.m. Type: ____ Submersible ____ Turbine ____ Jet ____ Reciprocating ____ Centrifugal ____ Other
18. Elevation:		19. Remarks: <u>Well in Basement.</u> <u>Well to be grouted with concrete</u> <u>3" larger than the outside Dia, 10 ft</u> <u>deep when pouring floor.</u> <u>Responsibility of Contractor</u> <u>to be disinfected upon pump installation.</u>		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Frotheroe Pumpwell 295</u> Business name <u>2372 W 27th St</u> License No. <u>Wichita</u> Address <u>2372 W 27th St</u> Signed <u>Frotheroe</u> Date <u>7-9-79</u> Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5