

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction center of SW 1/4 NW 1/4	Section number 19	Township number T 26 S	Range number R 21 E (W)
2. Distance and direction from nearest town or city: Street address of well location if in city: 1/4 W Maize			3. Owner of well: Don Weninger R.R. or street: City, state, zip code: Maize, Ks. 67101			
4. Locate with "X" in section below: Sketch map: open field			6. Bore hole dia. 30 in. Completion date 5/15/78 Well depth 78 ft.			
5. Type and color of material			7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary			
			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other			
			9. Casing: Material C. Asb. Height: <u>Above</u> or below Threaded ☐ Welded ☐ Surface 18 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 78 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 314			
			10. Screen: Manufacturer's name Johnson Type Cement-Asbestos 16" Slot/gauze 1/4" Length 39 Set between 39 ft. and 78 ft. Gravel pack? ☒ Size range of material 28			
			11. Static water level: <u>16</u> ft. below land surface Date 5/15/78 12. Pumping level below land surfaces: 26 ft. after 1 hrs. pumping 400 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 800 g.p.m.			
(Use a second sheet if needed)			13. Water sample submitted: ☐ Yes ☒ No Date ☐			
			14. Well head completion: ☐ Pitless adapter 18 inches above grade			
			15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.			
			16. Nearest source of possible contamination: ft. 700 Direction NW Type Domestic well Well disinfected upon completion? ☐ Yes ☒ No			
			17. Pump: Manufacturer's name Peerless Not installed Model number 8221 HP ☐ Volts ☐ Length of drop pipe 60 ft. capacity 450 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other			
18. Elevation: Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Irrigation 238 Business name Maize License No. ☐ Address Maize Signed Don Weninger Date 6/2/78 Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5

26-10-12
 T
R
S
C
1/4 1/4 1/4
 CASEW/WW