

1 LOCATION OF WATER WELL: Sedgwick	FRACTION NEAR $\frac{1}{4}$ CENTER OF SW $\frac{1}{4}$	Section Number 19	Township Number T 26 S	Range Number R 1W E/W																																																																						
Distance and direction from nearest town or city street address of well if located within city? 1/4 mile W. and 1/4 mile S. of Maize, Kansas Maize, Kansas																																																																										
2 WATER WELL OWNER: MAIZE SCHOOL DISTRICT #266 RR#, ST. ADDRESS, BOX #: 201 S. Park CITY, STATE, ZIP CODE: Maize, Kansas 67101																																																																										
Board of Agriculture, Division of Water Resource Application Number: 28.167																																																																										
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 	4 DEPTH OF COMPLETED WELL 67 ft. ground level Depth(s) groundwater Encountered 1 ft. 2 ft. 3 ft. WELL'S STATIC WATER LEVEL 27.55 FT. BELOW LAND SURFACE MEASURED ON 12/16/1994 Pump test data: Well water was 52.2 ft. after 1 hours pumping 224 gpm Est. Yield gpm: Well water was 52.5 ft. after 6 hours pumping 224 gpm Bore Hole Diameter 38 in. to ft. and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 5 Public water supply 8 Air conditioning 11 Injection well 2 Irrigation 4 Industrial 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No X ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes X No																																																																									
5 TYPE OF CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (Specify below) Welded X Threaded Blank casing Diameter 16 in. to 54 ft., Dia in. to ft., Dia in. to ft. Casing height above land surface 37 in., weight 72.80 lbs. / ft. Wall thickness or gauge No. .438 TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless Steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 other (specify) 12 None used (open hole) SCREEN OR PERFORATION OPENING ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) SCREEN-PERFORATION INTERVALS: from 54 ft. to 67 ft., From ft. to ft. from ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: from 49 ft. to 67 ft., From ft. to ft. from ft. to ft., From ft. to ft.																																																																										
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other 50/50 road sand & bentonite hole plug Grout Intervals: From 6 (cement grout) ft. to 20 ft. From 20 (other) ft. to 49 ft. From ft. to ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandon water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage None Apparent Direction from well? How many feet?																																																																										
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2">FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>2</td> <td></td> <td>topsoil</td> <td></td> <td></td> <td></td> </tr> <tr> <td>2</td> <td>12</td> <td></td> <td>brown clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>12</td> <td>32</td> <td></td> <td>sandy tan clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>32</td> <td>46</td> <td></td> <td>fine to coarse sand & fine to coarse gravel (loose)</td> <td></td> <td></td> <td></td> </tr> <tr> <td>46</td> <td>50</td> <td></td> <td>gray clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>50</td> <td>60</td> <td></td> <td>fine to coarse sand & fine gravel (loose & gray)</td> <td></td> <td></td> <td></td> </tr> <tr> <td>60</td> <td>64</td> <td></td> <td>gray clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>64</td> <td>67</td> <td></td> <td>fine to coarse sand & fine to coarse gravel</td> <td></td> <td></td> <td></td> </tr> <tr> <td>67</td> <td>69</td> <td></td> <td>yellow clay</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>					FROM		TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0	2		topsoil				2	12		brown clay				12	32		sandy tan clay				32	46		fine to coarse sand & fine to coarse gravel (loose)				46	50		gray clay				50	60		fine to coarse sand & fine gravel (loose & gray)				60	64		gray clay				64	67		fine to coarse sand & fine to coarse gravel				67	69		yellow clay			
FROM		TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																																																				
0	2		topsoil																																																																							
2	12		brown clay																																																																							
12	32		sandy tan clay																																																																							
32	46		fine to coarse sand & fine to coarse gravel (loose)																																																																							
46	50		gray clay																																																																							
50	60		fine to coarse sand & fine gravel (loose & gray)																																																																							
60	64		gray clay																																																																							
64	67		fine to coarse sand & fine to coarse gravel																																																																							
67	69		yellow clay																																																																							

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) **12/16/1994** and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **236** This Water Well Record was completed on (mo/day/yr) **12/29/94**
 Under the business name of **Harp Well & Pump Service, Inc.** by (signature) *Jane Grederick*