

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Pratt, Fraction 1/4 NE 1/4 SE 1/4, Section Number 23, Township No. T 26 S, Range Number R 11. Global Positioning System (GPS) information: Latitude: 37.769052, Longitude: -98.489235.

2 WATER WELL OWNER: Northern Natural Gas/ MW #4b, RR#, Street Address, Box #: P.O.Box 3330, City, State, ZIP Code : Omaha, NE 68103-0300. 3 LOCATE WELL WITH AN "X" IN SECTION BOX: [Diagram showing section box with 'X' in SE corner]. 4 DEPTH OF COMPLETED WELL 180 ft. Depth(s) Groundwater Encountered (1) 36 ft. (2) 180 ft. (3) 180 ft. WELL'S STATIC WATER LEVEL 36 ft. below land surface measured on mo/day/yr. 10/26/12.

5 TYPE OF CASING USED: Steel [X] PVC [ ] Other [ ]. CASING JOINTS: [ ] Glued [ ] Clamped [ ] Welded [ ] Threaded. Casing diameter .5 in. to .140 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface .24 in., Weight lbs./ft., Wall thickness or gauge No. Sch. 40. TYPE OF SCREEN OR PERFORATION MATERIAL: [ ] Steel [ ] Stainless Steel [ ] PVC [ ] Other (Specify) [ ]. SCREEN OR PERFORATION OPENINGS ARE: [ ] Continuous slot [X] Mill slot [ ] Gauze wrapped [ ] Torch cut [ ] Drilled holes [ ] None (open hole). SCREEN-PERFORATED INTERVALS: From 180 ft. to 140 ft., From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From 180 ft. to 100 ft., From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: [ ] Neat cement [ ] Cement grout [ ] Bentonite [ ] Other [ ]. Grout Intervals: From 100 ft. to 0 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: [ ] Septic tank [ ] Lateral lines [ ] Pit privy [ ] Livestock pens [ ] Insecticide storage [ ] Other (specify below). Direction from well North, Distance from well 300 ft.

Table with 6 columns: FROM, TO, LITHOLOGIC LOG, FROM, TO, LITHO. LOG (cont.) or PLUGGING INTERVALS. Rows include: 0-2 Silty Top Soil, 2-25 Layered Clays, 25-90 Sand & Gravel/Clay Layers, 90-95 Tan Shale, 95-110 Sand/Gravel, 110-118 Weathered Red/Grey Shale, 118-142 Sand/Gravel, 142-155 Cemented Sand/Shale Layers, 155-180 Red Shale.

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was [ ] constructed, [ ] reconstructed, or [ ] plugged under my jurisdiction and was completed on (mo/day/year) 11/12/12 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 665. This Water Well Record was completed on (mo/day/year) 11/20/12 under the business name of Pratt Well Service, Inc. by (signature) [Signature]

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html.