

1 LOCATION OF WATER WELL: County: Pratt Fraction NW 1/4 SW 1/4 SW 1/4 Section Number 8 Township Number T 26 S Range Number R 11W E/W

Distance and direction from nearest town or city street address of well if located within city? 2 N of Preston, Kansas

2 WATER WELL OWNER: Paul Jorns Eagle Drilling Jorns #1 RR#, St. Address, Box #: Route 1 Box 8609 Board of Agriculture, Division of Water Resources City, State, ZIP Code: Preston, Ks. 67569 Wichita, Kansas 67208 Application Number: T88-253

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: [Diagram of a 2x2 grid with NW, NE, SW, SE quadrants and an 'X' in the SW quadrant] 4 DEPTH OF COMPLETED WELL: 125 ft. ELEVATION: Unknown. WELL'S STATIC WATER LEVEL: 35 ft. below land surface measured on mo/day/yr 5/14/88.

5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped. 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded. 7 Fiberglass Threaded.

Blank casing diameter: 5 in. to 105 ft., Dia. Casing height above land surface: 12 in., weight 2.8 lbs./ft. Wall thickness or gauge No. Sch. 40.

TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify). 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole).

SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole). 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 12 Other (specify).

SCREEN-PERFORATED INTERVALS: From 105 ft. to 125 ft. GRAVEL PACK INTERVALS: From 10 ft. to 125 ft.

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other. Grout intervals: From 0 ft. to 20 ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well.

Direction from well? South. Table with columns FROM, TO, LITHOLOGIC LOG. Rows: 0-30 Clay, 30-80 Sandy Clay, 80-125 Sand and gravel.

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 5/14/88 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 186. This Water Well Record was completed on (mo/day/yr) 6/27/88.

under the business name of Kelly's Water Well Service by (signature) Dean Jorns. INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY

T

2

R

1

1

EW

SEC.

2

1/4

1/4

1/4