

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Pratt</b>	Fraction <b>C 1/4 SW 1/4 NW 1/4</b>	Section number <b>28</b>	Township number <b>T 26 S R 11 E/W</b>	Range number
2. Distance and direction from nearest town or city: <b>1 East-1/2 South of Preston, Ks.</b>			3. Owner of well: <b>B &amp; B Drilling Co.</b> R.R. or street: <b>515 Union Center</b> City, state, zip code: <b>Wichita, Ks. 67202</b>		
4. Locate with "X" in section below: <div style="text-align: center;"> </div>			Sketch map:		
5. Type and color of material			From	To	6. Bore hole dia. <b>8</b> in. Completion date _____ Well depth <b>173</b> ft. <b>6/11/77</b>
Sandy top soil			0	3	7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary
Brown and white clay			3	28	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Sand and gravel			28	38	9. Casing: Material <b>pvc</b> Height: Above or <del>Below</del> _____ Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>18</b> in. RMP _____ PVC <input checked="" type="checkbox"/> Weight <b>200</b> lbs./ft. Dia. <b>4</b> in. to <b>145</b> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. <b>237</b>
Brown and white clay			38	47	10. Screen: Manufacturer's name <b>Certainfeed</b> Type <b>pvc</b> Dia. <b>4</b> in. Slot <del>1/16</del> <b>1/16</b> Length <b>28</b> in. Set between <b>145</b> ft. and <b>173</b> ft. _____ ft. and _____ ft.
Sand and gravel Coarse and loose			47	59	11. Static water level: _____ mo./day/yr. <b>40</b> ft. below land surface Date <b>6/10/77</b>
Brown and gray clay			59	72	12. Pumping level below land surfaces: <b>na</b> _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.
Sand and gravel			72	74	13. Water sample submitted: _____ mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date _____
Brown and gray clay			74	95	14. Well head completion: <input type="checkbox"/> Pitless adapter <b>18</b> inches above grade
Sand and gravel Medium and loose			95	103	15. Well grouted? <b>no</b> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From _____ ft. to _____ ft.
Brown and white and gray clay			103	120	16. Nearest source of possible contamination: ft. <b>800</b> Direction <b>NW</b> Type <b>Septic</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No
Black, hard clay			<del>120</del>	<del>125</del>	17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Fine sand, sand clay mixed			125	150	
Sand and gravel Clean, coarse and loose			150	173	
Red bed			173	175	
(Use a second sheet if needed)					
18. Elevation: <b>1837'</b>	19. Remarks: Well will be pulled and plugged with well cuttings and gravel pack.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Rosencrantz-Bemis</b> <b>135</b> Business name License No. Address <b>Great Bend, Ks 67530</b> Signed <b>Sandy Hilgare</b> Date <b>6-13-77</b> Authorized representative		

T 26 S R 11 E  
 Sec 28  
 1/4 1/4 1/4 1/4  
 CSW MW

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5