

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Pratt</b>	Fraction <b>1/4 1/4 CSW 1/4</b>	Section number <b>23</b>	Township number <b>T 26 S R 12</b>	Range number <b>12</b>
2. Distance and direction from nearest town or city: <b>2 1/2 mi. West of Preston, Kansas</b> Street address of well location if in city:			3. Owner of well: <b>Merle Trinkle</b> R.R. or street: <b>Route 1</b> City, state, zip code: <b>Preston, KS 67569</b>		
4. Locate with "X" in section below:		Sketch map:			
5. Type and color of material		From	To	6. Bore hole dia. <u>24</u> in. Completion date <u>9-17-75</u> Well depth <u>145</u> ft.	
Top soil		0	3	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary	
Brown & gray clay		3	37	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Sand, fine gravel & clay streaks		37	81	9. Casing: Material <u>Steel</u> Height <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>30.3</u> lbs./ft. Dia. <u>16</u> in. to <u>85</u> ft. depth Wall Thickness: inches or Dia. <u>   </u> in. to <u>   </u> ft. depth gage No. <u>7 ga.</u>	
White clay		81	83	10. Screen: Manufacturer's name <u>W. A. Brown</u> Type <u>Double-slot</u> Dia. <u>16"</u> <u>1/8</u> Slot gage Length <u>60'</u> Set between <u>85</u> ft. and <u>145</u> ft. <u>   </u> ft. and <u>   </u> ft. Gravel pack? <u>Yes</u> Size range of material <u>3/8-200</u>	
Sand & gravel		83	99	11. Static water level: <u>33</u> ft. below land surface Date <u>9-17-75</u> mo./day/yr.	
Brown & white clay & limestone		99	108	12. Pumping level below land surfaces: <u>N/C</u> <u>   </u> ft. after <u>   </u> hrs. pumping <u>   </u> g.p.m. <u>   </u> ft. after <u>   </u> hrs. pumping <u>   </u> g.p.m. Estimated maximum yield <u>   </u> g.p.m.	
Sand, gravel & clay streaks at 127'		108	144	13. Water sample submitted: <u>   </u> mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <u>   </u>	
Brown clay		144	145	14. Well head completion: <input type="checkbox"/> Pitless adapter <u>12</u> Inches above grade	
				15. Well grouted? <u>Yes</u> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
				16. Nearest source of possible contamination: ft. <u>   </u> Direction <u>   </u> Type <u>   </u> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
				17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <u>   </u> Model number <u>   </u> HP <u>   </u> Volts <u>   </u> Length of drop pipe <u>   </u> ft. capacity <u>   </u> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
				20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Clarke Well &amp; Eq., Inc.</b> <u>185</u> Business name License No. Address <u>Great Bend, KS</u> Signed <u>[Signature]</u> Date <u>9-17-75</u> Authorized Representative	
18. Elevation:		19. Remarks:			
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5