

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Pratt	Fraction SW 1/4 NW 1/4 SW 1/4	Section number 11	Township number T 26 S R 13	Range number EW
2. Distance and direction from nearest town or city: 4 1/2 mi. N & 1 mi E Bob Moore XXXXXXXXXXXXXXX of Iuka, KS Street address of well location if in city:			3. Owner of well: Bob Moore R.R. or street: Route 1 - Box 27 City, state, zip code: Iuka, KS 67066			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>9</u> in. Completion date <u>2/27/79</u> Well depth <u>70</u> ft.		
				7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input checked="" type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Sandy top soil		0	3	9. Casing: Material <u>Styr</u> Height: <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>1.5</u> lbs./ft. Dia. <u>5</u> in. to <u>60</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>200</u>		
Sandy & brown clay		3	14	10. Screen: Manufacturer's name <u>Jess & Lowell</u> Type <u>Styrene 200</u> Dia. <u>5"</u> <u>Slot</u> gauze <u>1/8"</u> Hole Length <u>10'</u> Set between <u>60</u> ft. and <u>70</u> ft. <u> </u> ft. and <u> </u> ft. Gravel pack? <u>Yes</u> Size range of material <u>3/8-200</u>		
Gray & yellow clay		14	33	11. Static water level: <u>19</u> ft. below land surface Date <u>2/27/79</u> mo./day/yr.		
Fine sand		33	35	12. Pumping level below land surfaces: <u>Field</u> <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.		
Yellow clay		35	52	13. Water sample submitted: <u> </u> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u> </u>		
Fine sand		52	60	14. Well head completion: <input type="checkbox"/> Pitless adapter <u>12</u> inches above grade		
Sand & gravel		60	73	15. Well grouted? <u>Yes</u> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
(Use a second sheet if needed)				16. Nearest source of possible contamination: <u>FIELD</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: Manufacturer's name <u>Midwest</u> Not installed Model number <u>3"</u> HP <u> </u> Volts <u> </u> Length of drop pipe <u>42</u> ft. capacity <u> </u> g.p.m. Type: <input checked="" type="checkbox"/> Pump Cylinder & Pump Jack <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. <u> </u> Address <u>Great Bend, KS 67530</u> Signed <u>[Signature]</u> Date <u>2/27/79</u> Authorized representative			
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						

T
R
W
L
S
1/4
1/4
1/4
1/4
S
W
N
E
1/4
1/4
1/4
1/4