

USE TYPEWRITER OR BALL POINT PEN. PRESS FIRMLY. PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Pratt	Fraction 1/4 1/4 CNW 1/4	Section number 7	Township number T 26 S R	Range number 14 EW
----------------------	------------------------	------------------------------------	----------------------------	------------------------------------	------------------------------

2. Distance and direction from nearest town or city: 3 miles Northwest of Byers, KS Street address of well location if in city:	3. Owner of well: James R. Abrams R.R. or street: 923 Champa City, state, zip code: Pratt, KS 67124
--	---

4. Locate with "X" in section below: Sketch map:

N

NW	NE
SW	SE

S

1 Mile

6. Bore hole dia. 24 in. Completion date 12-15-76
Well depth 116 ft.

7. Cable tool Rotary Driven Dug
 Hollow rod Jetted Bored Reverse rotary

8. Use: Domestic Public supply Industry
 Irrigation Air conditioning Stock
 Lawn Oil field water Other

9. Casing: Material steel Height Above or below
Threaded Welded Surface 12 in.
RMP PVC Weight 30.3 lbs./ft.
Dia. 16 in. to 60 ft. depth Wall Thickness: inches or
Dia. 16 in. to 90 ft. depth gage No. 7 ga.

5. Type and color of material	From	To
top soil	0	4
gray clay	4	23
brown & white clay & limestone	23	44
sand & gravel	44	52
brown clay	52	59
sand & gravel	59	77
blue, gray clay, & limestone	77	91
sand & gravel	91	116
(Use a second sheet if needed)		

10. Screen: Manufacturer's name Doerr
Type double-slot Dia. 16"
Slot/gauze 1/8" Length 46'
Set between 60 ft. and 80 ft.
90 ft. and 116 ft.
Gravel pack? yes Size range of material 3/8-200

11. Static water level: 18'6" ft. below land surface Date 11-20-76 mo./day/yr.

12. Pumping level below land surfaces: N/C
____ ft. after ____ hrs. pumping ____ g.p.m.
____ ft. after ____ hrs. pumping ____ g.p.m.
Estimated maximum yield ____ g.p.m.

13. Water sample submitted: ____ mo./day/yr.
 Yes No Date ____

14. Well head completion:
 Pitless adapter 12 inches above grade

15. Well grouted? yes
With: Neat cement Bentonite Concrete
Depth: From 0 ft. to 10 ft.

16. Nearest source of possible contamination:
ft. ____ Direction ____ Type ____
Well disinfected upon completion? Yes No

17. Pump: Not installed
Manufacturer's name Peerless Pump
Model number 12LB-3 HP 80 Volts ---
Length of drop pipe 70 ft. capacity 900 g.p.m.
Type:
 Submersible Turbine
 Jet Reciprocating
 Centrifugal Other

18. Elevation: Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley	19. Remarks: 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Equip., Inc. 185 Business name <u>Great Bend, KS 67530</u> License No. <u>---</u> Address <u>---</u> Signed <u>C.W. Clarke</u> Date <u>12-17-76</u> Authorized representative
--	---

T 26
 R 14
 E 7
 Sec 7
 1/4
 1/4
 1/4
 1/4
 C.W.