

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

| | | | | | |
|--|------------------------|--------------------------------------|---|---------------------------------------|---|
| 1. Location of well: | County Pratt | Fraction 1/4 SW 1/4 NW 1/4 | Section number 24 | Township number T 26 S R 15 | Range number EW |
| 2. Distance and direction from nearest town or city: 3 3/4 miles Southwest of Byers, KS Street address of well location if in city: | | | 3. Owner of well: Ivan Stotts R.R. or street: (?) City, state, zip code: Byers, KS 67021 | | |
| 4. Locate with "X" in section below: N 1 Mile W E S 1 Mile | | | Sketch map: | | |
| 5. Type and color of material | | | From | To | 6. Bore hole dia. <u>9</u> in. Completion date <u>6-15-78</u> Well depth <u>60</u> ft. Pump Set <u>7-25-78</u> |
| Top soil | | | 0 | 3 | 7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary |
| Gray clay | | | 3 | 9 | 8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other |
| Brown & white clay & limestone | | | 9 | 38 | 9. Casing: Material <u>Styrene</u> Height <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>1.5</u> lbs./ft. Dia. <u>5</u> in. to <u>40</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>XXX .200</u> |
| Sand & gravel | | | 38 | 60 | 10. Screen: Manufacturer's name <u>Jess & Lowell</u> Type <u>Styrene 200</u> Dia. <u>5"</u> Slot gauze <u>1/8"</u> Length <u>20'</u> Set between <u>40</u> ft. and <u>60</u> ft. <u> </u> ft. and <u> </u> ft. Gravel pack? <u>Yes</u> Size range of material. <u>3/8-200</u> |
| | | | | | 11. Static water level: <u>21'6"</u> ft. below land surface Date <u>6-15-78</u> mo./day/yr. |
| | | | | | 12. Pumping level below land surfaces: <u>N/C</u> <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m. |
| | | | | | 13. Water sample submitted: <u> </u> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u> </u> |
| | | | | | 14. Well head completion: <input type="checkbox"/> Pitless adapter <u>12</u> inches above grade |
| | | | | | 15. Well grouted? <u>Yes</u> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft. |
| | | | | | 16. Nearest source of possible contamination: <u>FIELD</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No |
| | | | | | 17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>Berkeley Pump Co.</u> Model number <u>4BL-12</u> HP <u>3/4</u> Volts <u>230</u> Length of drop pipe <u>42</u> ft. capacity <u>15</u> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other |
| (Use a second sheet if needed) | | | | | |
| 18. Elevation: | 19. Remarks: | | 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name <u>Great Bend, KS 67530</u> License No. <u> </u> Address <u> </u> Signed <u> </u> Date <u>7-26-78</u> Authorized representative | | |
| Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley | | | | | |

T 26 S R 15 E
Sec 24
1/4 1/4 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5