

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

| | | | | | |
|---|--------------------------|---|---|---|--|
| 1. Location of well: | County <i>Edwards</i> | Fraction <i>Lots 3&4</i> <i>SW 1/4 SW 1/4 NW 1/4</i> | Section number <i>1</i> | Township number <i>T 26 S R 16 E/W</i> | Range number |
| 2. Distance and direction from nearest town or city: <i>95 - 3 1/2 W - 1/2 S from Macksville, ks</i> | | | 3. Owner of well: <i>H. E. Curtis</i> R.R. or street: <i>none</i> City, state, zip code: <i>Haviland, ks 67059</i> | | |
| 4. Locate with "X" in section below: N W <i>X</i> E S 1 Mile 1 Mile | | | Sketch map: | | |
| 5. Type and color of material | | | From | To | 6. Bore hole dia. <i>11</i> in. Completion date Well depth <i>80</i> ft. <i>8-2-77</i> |
| <i>Top soil</i> | | | <i>0</i> | <i>2</i> | 7. <input checked="" type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary |
| <i>Sandy brown clay</i> | | | <i>2</i> | <i>5</i> | 8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other |
| <i>Sand & gravel - dirty</i> | | | <i>5</i> | <i>9</i> | 9. Casing: Material <i>pvc</i> Height: Above or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <i>18</i> in. RMP <input type="checkbox"/> PVC <input checked="" type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <i>4</i> in. to <i>80</i> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <i>237</i> |
| <i>Brown & white sandy clay</i> | | | <i>9</i> | <i>37</i> | 10. Screen: Manufacturer's name <i>Certainfeed</i> Type <i>pvc</i> Dia. <i>4 1/2"</i> Slot/gauge <i>1/16</i> Length <i>80</i> Set between <i>60</i> ft. and <i>80</i> ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <i>1/2 3/4"</i> |
| <i>Sand & gravel</i> | | | <i>37</i> | <i>41</i> | 11. Static water level: <input type="checkbox"/> mo./day/yr. <i>17</i> ft. below land surface Date <i>8-2-77</i> |
| <i>Brown & white clay</i> | | | <i>41</i> | <i>47</i> | 12. Pumping level below land surfaces: <i>17 1/2</i> ft. after <i>1</i> hrs. pumping <i>60</i> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <i>60</i> g.p.m. |
| <i>Sandy brown & white clay little</i> | | | <i>47</i> | <i>55</i> | 13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <i>8-3-77</i> |
| <i>Sand & gravel mixed</i> | | | | | 14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> inches above grade |
| <i>Sand & gravel clean, coarse base</i> | | | <i>55</i> | <i>80</i> | 15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <i>0</i> ft. to <i>10</i> ft. |
| | | | | | 16. Nearest source of possible contamination: ft. <i>300</i> Direction <i>North</i> Type <i>cornmill</i> Well disinfected upon completion? <i>HHH</i> Yes <input type="checkbox"/> No |
| | | | | | 17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other |
| (Use a second sheet if needed) | | | | | |
| 18. Elevation: | 19. Remarks: | | 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <i>Rosecrantz-Dennis 134</i> Business name _____ License No. _____ Address <i>West Bend, ks 67530</i> Signed <i>Sandy Kilgore</i> Date <i>9-4-77</i> Authorized representative | | |
| Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley | | | | | |

T 26 S R 16 E
 Sec 1
 SUSANNA

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5