


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Edwards</b>	Fraction <b>1/4 1/4 1/4</b>	Section number <b>21</b>	Township number <b>T 26 S</b>	Range number <b>R 17 E/W</b>
2. Distance and direction from nearest town or city: <b>135 3/4 W 1/4 N 1/4 E Fellsburg</b> Street address of well location if in city:				3. Owner of well: <b>Norman Nelson</b> R.R. or street: City, state, zip code: <b>Long Island, Ks.</b>		
4. Locate with "X" in section below: <div style="text-align: center;">N 1 Mile W  E S 1 Mile</div>				Sketch map:		
5. Type and color of material				From	To	6. Bore hole dia. <b>24</b> in. Completion date <b>11-11-75</b> Well depth <b>168</b> ft.
Sandy Top Soil				0	2	7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary
Brown & Gray Clay				2	9	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Fine Sand & Gravel lot of Clay				9	15	X Casing: Material <b>Steel</b> Height: <b>Above</b> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>8</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <b>16</b> in. to <b>168</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>1</b>
Fine Sand				15	20	10. Screen: Manufacturer's name <b>Doerr</b> Type <b>Steel</b> Dia. <b>16</b> Slot/gauge <b>3/16</b> Length <b>48</b> Set between <b>120</b> ft. and <b>168</b> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1/2 3/4 1 1/2</b>
Brown Sandy Clay				20	27	11. Static water level: <b>14</b> ft. below land surface Date <b>10-9-75</b>
Sand & Gravel Clean Coarse loose				27	69	12. Pumping level below land surfaces: <b>15</b> ft. after <b>1</b> hrs. pumping <b>1000</b> g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <b>1200</b> g.p.m.
Yellow Brown Clay				69	72	13. Water sample submitted: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <b>10-23-75</b>
Sand & Gravel Clean Coarse loose				72	96	14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade
Brown & White Clay				96	103	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.
Brown & White Clay with Sand Streaks				103	106	16. Nearest source of possible contamination: ft. <b>3/4</b> Direction <b>nw</b> Type <b>septic tank</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No
Sand & Gravel				106	108	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <b>WER</b> Model number <b>4-CM-12</b> HP <b>30</b> Volts <input type="checkbox"/> Length of drop pipe <b>70</b> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
HARD White Rock				108	109	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Rosenkrantz - Bemis 134</b> Business name <b>Great Bend, Ks.</b> License No. Address <b>Fredia Redern</b> Signed <b>9/29/74</b> Date <b>9/29/74</b> Authorized representative
Sand & Gravel with Sand Streaks				109	120	
Sand & Gravel Clean Coarse loose				120	168	
Brown & White Clay				168	172	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:				
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5