


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Edwards</b>	Fraction <b>1/4 c 1/4 nw 1/4</b>	Section number <b>29</b>	Township number <b>T 26 S</b>	Range number <b>R 17 <del>EW</del></b>
2. Distance and direction from nearest town or city: <b>4 south, 2 west of Fellsburg, Ks.</b> Street address of well location if in city:			3. Owner of well: <b>Midwest Land &amp; Cattle Co.</b> R.R. or street: <b>Box 64</b> City, state, zip code: <b>Kinsley, Ks. 67547</b>		
4. Locate with "X" in section below: <div style="text-align: center;">  </div>			Sketch map:		
5. Type and color of material			From	To	6. Bore hole dia. <b>29</b> in. Completion date _____ Well depth <b>158</b> ft. <b>7-18-75</b>
Sandy top soil			0	2	7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary
Sandy brown clay			2	12	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Fine sand and sandy brown clay			12	16	9. Casing: Material <b>Steel</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight _____ lbs./ft. Dia. <b>16</b> in. to <b>158</b> depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth Gauge No. <b>7</b>
Brown & white clay			16	26	10. Screen: Manufacturer's name <b>Boerres</b> Type <b>steel</b> Dia. <b>16</b> Slot/groze <b>3/16</b> Length <b>40</b> Set between <b>118</b> ft. and <b>158</b> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>3/4-3/8-1/2</b>
Fine sand and clay			26	33	11. Static water level: _____ mo./day/yr. <b>15</b> ft. below land surface Date <b>5-20-75</b>
Yellow brown & white clay			33	40	12. Pumping level below land surfaces: _____ ft. after <b>1</b> hrs. pumping <b>900</b> g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <b>900</b> g.p.m.
Sand and gravel clean coarse loose			40	77	13. Water sample submitted: _____ mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <b>5-20-75</b>
Sandy brown and white clay			77	80	14. Well head completion: <input type="checkbox"/> Pitless adapter _____ inches above grade
Sand and gravel clean coarse loose			80	93	15. Well grouted? <input checked="" type="checkbox"/> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From _____ ft. to <b>10</b> ft.
Brown sandy clay			93	104	16. Nearest source of possible contamination: ft. <b>1320</b> Direction <b>north farmstead</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Hard white cemented sand			104	105 1/2	17. Pump: _____ Not installed Manufacturer's name <b>W.L.R.</b> Model number <b>4-12BH</b> HP <b>80</b> Volts _____ Length of drop pipe <b>70</b> ft. capacity <b>800</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
Brown & white sandy clay			105 1/2	107	
Sand and gravel clean coarse loose			107	158	
Yellow brown clay			158	161	
(Use a second sheet if needed)					
18. Elevation: <b>2142</b> Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley	19. Remarks: <b>31187</b> <b>26 17 29 NBX</b>				
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Rosencrantz-Bemis 134</b> Business name _____ License No. _____ Address <b>Great Bend, Ks. 67530</b> Signed <b>S. Kilgore</b> Date <b>6-19-75</b> Authorized representative					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5