


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Edwards</b>	Fraction <b>Center</b> 1/4 1/4 SW 1/4	Section number <b>29</b>	Township number <b>26</b> T S R	Range number <b>17</b> E W
2. Distance and direction from nearest town or city: <b>4 miles south and 1 1/2 miles west of Fellsburg, KS.</b>			3. Owner of well: <b>Vernon C. Brown</b> R.R. or street: <b>Route 2</b> City, state, zip code: <b>Lewis, KS 67552</b>		
4. Locate with "X" in section below: 			Sketch map:		
5. Type and color of material			From	To	6. Bore hole dia. <b>24</b> in. Completion date <b>12/14/76</b> Well depth <b>160</b> ft.
Sand			0	19	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
Yellow Clay			19	24	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
Sandy Clay			24	40	9. Casing: Material <b>Steel</b> Height: <b>Above</b> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>3.03</b> lbs./ft. Dia. <b>16</b> in. to <b>80</b> ft. depth Wall Thickness <b>7</b> inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <input type="checkbox"/>
White Clay, and Limestone			40	41	10. Screen: Manufacturer's name <b>Cook</b> Type <b>Double-slot</b> Dia. <b>16"</b> Slot gauge <b>1/8</b> Length <b>160'</b> Set between <b>80</b> ft. and <b>160</b> ft. ft. and <input type="checkbox"/> ft. Gravel pack? <b>yes</b> Size range of material <b>3/8-200</b>
Sand and Sandy Clay			41	49	11. Static water level: <b>39' 6"</b> ft. below land surface Date <b>12/14/76</b> mo./day/yr.
Yellow Clay			49	53	12. Pumping level below land surfaces: <b>NC</b> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <input type="checkbox"/> g.p.m.
Fine Sand and Clay Streaks			53	63	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>
Sand and Gravel and Thin Clay Streaks			63	116	14. Well head completion: Pitless adapter <b>12</b> inches above grade
Yellow Clay			116	121	15. Well grouted? <b>yes</b> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.
Fine Sand, Sand and Gravel			121	160	16. Nearest source of possible contamination: ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <b>FIELD</b> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Yellow Clay			160	161	17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number <input type="checkbox"/> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe <input type="checkbox"/> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
(Use a second sheet if needed)					
18. Elevation:  Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley	19. Remarks: <b>This report is late because the log was overlooked in our files.</b>			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Clarke Well &amp; Equipment, Inc.</b> Business name <b>Great Bend, KS</b> License No. <b>67530</b> Address <b>2/1/77</b> Signed <b>[Signature]</b> Date <b>2/1/77</b> Authorized representative	

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5