

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 024 EDWARDS NE 1/4 NE 1/4 SE 1/4 29 T 26 S R 17 W

Distance and direction from nearest town or city street address of well if located within city?  
 4 S. 1 W. OF FELLSBURG, KS

2 WATER WELL OWNER: TOM STEJSKAL 293  
 RR#, St. Address, Box #: R.R. 1, 84 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code : LEWIS, KS 67552- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4
NW	NE	SW	SE
			X

4 DEPTH OF COMPLETED WELL 115 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 29 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 29 ft. below land surface measured on mo/day/yr  
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 8.75 in. to 115 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 100 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 100 ft. to 115 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 115 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 4 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 01 SEPTIC TANK  
 Direction from well? SE How many feet? 75

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	6	BROWN CLAY			
6	10	TAN CLAY			
10	18	05 SAND			
18	28	TAN CLAY			
28	95	05 SAND AND 17 GRAVEL			
95	100	TAN CLAY			
100	115	05 SAND AND 17 GRAVEL			
115	116	TAN CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/1 /94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 12/18/94 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse