


18
USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well: County <u>Edwards</u>		Fraction <u>C/NE</u> 1/4 1/4 1/4	Section number <u>27</u>	Township number <u>T 26</u>	Range number <u>S R 18 E/W</u>	
2. Distance and direction from nearest town or city: <u>3 1/2 mi. of Centerview W side Rd. 1/4 W</u> Street address of well location if in city:			3. Owner of well: <u>Carl Donovan</u> R.R. or street: <u>3408 East Main #1610</u> City, state, zip code: <u>Nesa, Arizona</u>			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile		Sketch map: 		6. Bore hole dia. <u>20</u> in. Completion date <u>12-29-76</u> Well depth <u>152</u> ft.		
5. Type and color of material		From	To	7. <input checked="" type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
<u>Sandy Top Soil</u>		<u>0</u>	<u>4</u>	8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
<u>Brown Sandy Clay</u>		<u>4</u>	<u>10</u>	9. Casing: Material <u>steel</u> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>18</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <u>16</u> in. to <u>152</u> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <u>7</u>		
<u>Brown White Clay</u>		<u>10</u>	<u>20</u>	10. Screen: Manufacturer's name <u>Doerrs</u> Type <u>steel</u> Dia. <u>16</u> Slot <u>3/16</u> Dia. <u>684</u> Length <u>684</u> Set between <u>684</u> ft. and <u>152</u> ft. <u>684</u> ft. and <u>152</u> ft.		
<u>Med. Coarse Sand & Gravel</u>		<u>20</u>	<u>30</u>	Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>3/4" to 3/8"</u>		
<u>Sand Gravel</u>		<u>30</u>	<u>40</u>	11. Static water level: <u>24</u> ft. below land surface Date <u>9-18-76</u>		
<u>White Clay</u>		<u>40</u>	<u>43</u>	12. Pumping level below land surfaces: <u>26</u> ft. after <u>1</u> hrs. pumping <u>800</u> g.p.m. <u>26</u> ft. after <u>1</u> hrs. pumping <u>800</u> g.p.m. Estimated maximum yield <u>1000</u> g.p.m.		
<u>White Clay Sand & Gravel</u>		<u>43</u>	<u>48</u>	13. Water sample submitted: <u>X</u> Yes <input type="checkbox"/> No Date <u>8-29-76</u>		
<u>Sand Gravel</u>		<u>48</u>	<u>70</u>	14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade		
<u>Brown Clay</u>		<u>70</u>	<u>80</u>	15. Well grouted? <input checked="" type="checkbox"/> <u>X</u> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
<u>Sand Gravel</u>		<u>80</u>	<u>102</u>	16. Nearest source of possible contamination: ft. <u>4 m</u> Direction <u>N</u> Type <u>Carroll</u> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No		
<u>Brown White Clay</u>		<u>102</u>	<u>110</u>	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>Western Land Roller</u> Model number <u>4KBH2-12</u> HP <u>80</u> Volts <u>120</u> Length of drop pipe <u>100</u> ft. capacity <u>1200</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
<u>Sand Gravel</u>		<u>125</u>	<u>155</u>	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosencrantz-Bemis 134</u> Business name <u>Great Bend, Ks.</u> License No. Address <u>2/23/77</u> Signed <u>Freddie Anderson</u> Date <u>2/23/77</u> Authorized representative		
<u>Red Brown Clay</u>		<u>155</u>	<u>170</u>			
<u>Yellow Br. White Clay</u>		<u>170</u>	<u>185</u>			
18. Elevation: <u>2176'</u> Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		19. Remarks: <u>(See a second sheet if needed)</u>				

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5