


USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment (Water well Contractors) Topeka, Kansas 66620

1. Location of well:		County Edwards	Fraction SE 1/4 1/4 1/4	Section number 32	Township number T 26 S R 18 NE/W	Range number	
2. Distance and direction from nearest town or city: 6 mi. South & 2 West of Centerview			3. Owner of well: Bill Chadd Greensburg, Kansas				
4. Locate with "X" in section below: 			Sketch map: Well No. 2 (TH 4-76)		6. Bore hole dia. <u>30</u> in. Completion date <u>5/8/76</u> Well depth <u>162</u> ft.		
5. Type and color of material			From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
Sandy soil			0	2	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Clay			2	13	9. Casing: Material <u>Stl</u> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>36.91</u> lbs./ft. Dia. <u>16</u> in. to <u>117</u> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <u>219</u>		
Sand & Gravel			13	25	10. Screen: Manufacturer's name <u>Doerr Metal Products</u> Type <u>Stl.</u> Dia. <u>16"</u> Slot/gauze <u>1/8"</u> Length <u>48'</u> Set between <u>88</u> ft. and <u>108</u> ft. <u>134</u> ft. and <u>162</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/8-1/2</u>		
Clay			25	50	11. Static water level: <u>29</u> ft. below land surface Date <u>6-28-76</u> mo./day/yr.		
Med. to coarse sand & gravel			50	73	12. Pumping level below land surfaces: <u>48</u> ft. after <u>3</u> hrs. pumping <u>1002</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>1500</u> g.p.m.		
Clay			73	84	13. Water sample submitted: <u> </u> mo./day/yr. Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Date <u> </u>		
Med. to coarse sand & gravel			84	108	14. Well head completion: <input type="checkbox"/> Pitless adapter <u>12</u> inches above grade		
Clay			108	128	15. Well grouted? <u>yes</u> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
Med. to coarse sand & gravel			128	161	16. Nearest source of possible contamination: ft. <u>6000</u> Direction <u>South</u> Type <u>Farm</u> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		
Clay			161	165	17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>Layne</u> Model number <u>12 KM</u> HP <u>30</u> Volts <u> </u> Length of drop pipe <u>30</u> ft. capacity <u>900</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Layne Western Co. 102 Business name <u>Wichita Kansas</u> License No. <u> </u> Address <u> </u> Signed <u> </u> Date <u>7/2/76</u> Authorized representative		
18. Elevation:		19. Remarks:				20. Water well contractor's certification:	
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley							

T
R
E
S
S
E
S
E
1/4
1/4
1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5