

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: EDWARDS SW 1/4 SW 1/4 NE 1/4 35 T 26 S R 18 W

Distance and direction from nearest town or city street address of well if located within city?

4 1/2 MILES SOUTH, 1/2 MILE EAST, 1/2 MILE SOUTH OF CENTERVIEW

2 WATER WELL OWNER: NEFF, REX
 RR#, St. Address, Box #: RR2 BOX 37

Board of Agriculture, Division of Water Resources

City, State, ZIP code : LEWIS, KS 67552-

Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

	NW	NE	
		X	
	SW	SE	

4 DEPTH OF COMPLETED WELL 120 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 38 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 38 ft. below land surface measured on mo/day/yr 10/15/01
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8.75 in. to 120 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;

If yes, mo/day/yr sample was submitted

Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC

CASING JOINTS: GLUED

Blank casing diameter 5 in. to 110 ft., Dia in. to 0 ft., Dia in. to 0 ft.

Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26

TYPE OF SCREEN OR PERFORATION MATERIAL: PVC

SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 110 ft. to 120 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

GRAVEL PACK INTERVALS: From 25 ft. to 120 ft., From 0 ft. to 0 ft.

From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE

Grout Intervals: From 4 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.

What is the nearest source of possible contamination: SEPTIC TANK

Direction from well? NORTHWEST

How many feet? 400

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	40	TAN CLAY			
40	70	SAND AND CLAY			
70	82	SAND AND GRAVEL			
82	85	SAND			
85	91	WHITE CLAY			
91	93	GRAVEL			
93	108	BROWN CLAY			
108	120	SAND AND GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/15/01 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 11/17/01 under the business name of DAN HAYSE WATER WELL SVC. by (signature) Don Hayse