

189

1 LOCATION OF WATER WELL: COUNTY: EDWARDS	Fraction NW 1/4 NW 1/4 SE 1/4	Section Number 29	Township Number T 26 S	Range Number R 18 W
--	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?  
1 MILE WEST, 10 MILES NORTH, 1/2 MILE EAST OF GREENSBURG

2 WATER WELL OWNER: GAMBLE, NORMA LEE  
RR#, St. Address, Box #: 715-A STACKMAN DRIVE Board of Agriculture, Division of Water Resources  
City, State, ZIP code: WICHITA, KS 67203- Application Number:

3 LOCATE WELL'S LOCATION WITH  
AN "X" IN SECTION BOX:

/ \					
1	---	NW	---	NE	---
M	W		X		E
i					
l					
e					
\ /					

4 DEPTH OF COMPLETED WELL 110 ELEVATION: 0  
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 48 ft. below land surface measured on mo/day/yr 12/28/03  
Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8.75 in. to 110 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED  
Blank casing diameter 5 in. to 90 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
Casing height above land surface 12 in., weight 0 lbs/ft. Wall thickness or gauge No. 26  
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS:	From 90 ft. to 110 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 26 ft. to 75 ft.,	From 0 ft. to 0 ft.
	From 80 ft. to 110 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
Grout Intervals: From 4 ft. to 26 ft., From 75 ft. to 80 ft., From 0 ft. to 0 ft.  
What is the nearest source of possible contamination: SEPTIC TANK  
Direction from well? EAST How many feet? 70

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	SILT AND SAND			
2	12	BROWN CLAY			
12	75	SAND AND GRAVEL			
75	86	TAN CLAY			
86	105	SAND AND GRAVEL			
105	110	TAN CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 12/28/03 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 03/01/04  
under the business name of DAN HAYSE WATER WELL SERV by (signature) Dan Hayse