

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well: County <u>Edwards</u>		Fraction <u>1/4 C 1/4 NW 1/4</u>		Section number <u>4</u>		Township number <u>T 26 S R 19 E/W</u>		Range number <u>19</u>			
2. Distance and direction from nearest town or city: <u>6 1/4 So. of Kinsey, Ks.</u> Street address of well location if in city:				3. Owner of well: <u>Mid America Land Co.</u> R.R. or street: <u>5102 East 21st St</u> City, state, zip code: <u>Wichita, Ks</u>							
4. Locate with "X" in section below: N W E S 1 Mile				Sketch map: 		6. Bore hole dia. <u>29</u> in. Completion date <u>4-28-77</u> Well depth <u>98</u> ft.		7. <input type="checkbox"/> Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
5. Type and color of material				From		To		9. Casing: Material <u>Steel</u> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. <u>16</u> in. to <u>98</u> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <u>70a</u>			
<u>Sandy top soil</u>				<u>0</u>		<u>2</u>		10. Screen: Manufacturer's name <u>Dalys</u> Type <u>slut</u> Dia. <u>16</u> Slot/gauze <u>3/16</u> Length <u>33</u> Set between <u>66</u> ft. and <u>99</u> ft. <input type="checkbox"/> ft. and <input type="checkbox"/> ft.			
<u>Fine sand</u>				<u>2</u>		<u>12</u>		Gravel pack? <input checked="" type="checkbox"/> Size range of material <u>3/4-3/8-6</u>			
<u>Brown Sandy clay</u>				<u>12</u>		<u>14</u>		11. Static water level: <u>38</u> ft. below land surface Date <u>2-9-77</u> mo./day/yr.			
<u>Brown + gray sandy clay</u>				<u>14</u>		<u>27</u>		12. Pumping level below land surfaces: <u>49</u> ft. after <u>1</u> hrs. pumping <u>600</u> g.p.m. <u>57</u> ft. after <u>2</u> hrs. pumping <u>1000</u> g.p.m. Estimated maximum yield <u>1400</u> g.p.m.			
<u>Sand + gravel</u>				<u>27</u>		<u>97</u>		13. Water sample submitted: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date <u>2-9-77</u> mo./day/yr.			
<u>Brown + white clay</u>				<u>97</u>		<u>120</u>		14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade			
								15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.			
								16. Nearest source of possible contamination: ft. <u>180</u> Direction <u>NW</u> Type <u>septic tank</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No			
								17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>W.D. K.</u> Model number <u>4-120M</u> HP <u>60</u> Volts <u>    </u> Length of drop pipe <u>80</u> ft. capacity <u>200</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other			
								20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosenrath - Bemis 134</u> Business name <u>Great Bend, Ks</u> License No. <u>    </u> Address <u>    </u> Signed <u>Sandy Kilgore</u> Date <u>5-19-77</u> Authorized representative			
18. Elevation:		19. Remarks:									
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley											

T 26 S R 19 E  
 Sec 4  
 NW 1/4  
 NE 1/4

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5