


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <u>Edwards</u>	Fraction <u>C/SW</u> 1/4 1/4 1/4	Section number <u>34</u>	Township number <u>26</u> T S R	Range number <u>19</u> E/W
2. Distance and direction from nearest town or city: <u>8 N 34 E of Greensburg</u> Street address of well location if in city:			3. Owner of well: <u>Ed Miller</u> R.R. or street: <u>Ed Miller, Ks.</u> City, state, zip code: <u>Greensburg, KS.</u>			
4. Locate with "X" in section below: N W E S 1 Mile			Sketch map: 		6. Bore hole dia. <u>24</u> in. Completion date Well depth <u>135</u> ft. <u>9-18-75</u>	
5. Type and color of material			From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary	
<u>Sandy Top Soil</u>			<u>0</u>	<u>2</u>	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
<u>Gray Clay</u>			<u>2</u>	<u>8</u>	9. Casing: Material <u>Steel</u> Height <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input type="checkbox"/> Surface <u>18</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft.	
<u>Sandy Brown Clay &amp; fine sand</u>			<u>8</u>	<u>15</u>	Dia. <u>16</u> in. to <u>135</u> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <u>7</u>	
<u>fine sand</u>			<u>15</u>	<u>20</u>	10. Screen: Manufacturer's name <u>Doerr</u> Type <u>Steel</u> Dia. <u>16</u> Slot size <u>3/16</u> Length <u>40</u> Set between <u>95</u> ft. and <u>135</u> ft. Gravel pack? <input type="checkbox"/> Size range of material <u>16 3/4 3/8</u>	
<u>sand &amp; gravel clean coarse loose</u>			<u>20</u>	<u>83</u>	11. Static water level: <u>37</u> ft. below land surface Date <u>8-29-75</u> mo./day/yr.	
<u>Yellow Brown Clay</u>			<u>83</u>	<u>84 1/2</u>	12. Pumping level below land surfaces: <u>38</u> ft. after <u>15 min</u> hrs. pumping <u>800</u> g.p.m. <u>    </u> ft. after <u>    </u> hrs. pumping <u>    </u> g.p.m. Estimated maximum yield <u>1000</u> g.p.m.	
<u>sand &amp; gravel clean coarse loose</u>			<u>84 1/2</u>	<u>100</u>	13. Water sample submitted: <u>Yes</u> <input checked="" type="checkbox"/> No <input type="checkbox"/> Date <u>9-5-75</u> mo./day/yr.	
<u>Brown &amp; White Clay</u>			<u>100</u>	<u>107</u>	14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> inches above grade	
<u>sand &amp; gravel clean coarse loose</u>			<u>107</u>	<u>133</u>	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
<u>Yellow Brown to Gray Clay</u>			<u>133</u>	<u>141</u>	16. Nearest source of possible contamination: ft. <u>14 m</u> Direction <u>NE</u> Type <u>Feed yard</u> Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No	
					17. Pump: Manufacturer's name <u>WLR</u> Not installed Model number <u>5CM12</u> HP <u>50</u> Volts <u>    </u> Length of drop pipe <u>80</u> ft. capacity <u>1000</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Rosenkrantz - Burns</u> <u>134</u> Business name License No. Address <u>Great Bend, KS.</u> Signed <u>Judith A. Norman</u> Date <u>9/2/75</u> Authorized representative	
18. Elevation:		19. Remarks:				
Topography: <input type="checkbox"/> Hill <input checked="" type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5