

1 LOCATION OF WATER WELL: Sedgwick	FRACTION <i>Center of S 1/2</i> 1/4 1/4 1/4	Section Number 3	Township Number T 26 S	Range Number R 2W E/W
--	---	----------------------------	----------------------------------	---------------------------------

Distance and direction from nearest town or city street address of well if located within city?

2 m. N., 1/2 m. E., 1/4 m. N. of Colwich, Kansas

WATER WELL OWNER: NEVILLE, Alvin	Board of Agriculture, Division of Water Resource
RR#, ST. ADDRESS, BOX #: 11304 W. 21st N.	
CITY, STATE, ZIP CODE: Wichita, Kansas	Application Number: 28,837

LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 	4 DEPTH OF COMPLETED WELL 116 ft. ELEVATION:
	Depth(s) groundwater Encountered 1 ft. 2 ft. 3 ft.
	WELL'S STATIC WATER LEVEL 19 FT. BELOW LAND SURFACE MEASURED ON 07/02/1997
	Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm
Est. Yield 1,000 gpm: Well water was _____ ft. after _____ hours pumping _____ gpm	
Bore Hole Diameter 30 in. to 116 ft. and _____ in. to _____ ft.	
WELL WATER TO BE USED AS:	
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)	
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well	
Was a chemical/bacteriological sample submitted to Department? Yes _____ No X ; If yes, mo/day/yr sample was submitted _____	
Water Well Disinfected? Yes X No _____	

5 TYPE OF CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued X Clamped
1 Steel 3 RMP (SR)	6 Asbestos-Cement	9 Other (Specify below)	Welded
2 PVC 4 ABS	7 Fiberglass	SDR-26	Threaded
Blank casing Diameter 16 in. to 77 ft., Dia _____ in. to _____ ft.			
Casing height above land surface 12 in., weight 19.75 lbs. / ft.		Wall thickness or gauge No. .616	
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel 3 Stainless Steel 5 Fiberglass 8 RMP (SR) 11 other (specify)			
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)			
SCREEN OR PERFORATION OPENING ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes			
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)			
SCREEN-PERFORATION INTERVALS: from 77 ft. to 116 ft., From _____ ft. to _____ ft.			
GRAVEL PACK INTERVALS: from 20 ft. to 116 ft., From _____ ft. to _____ ft.			

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other cement & bentonite	
Grout Intervals: From 0 ft. to 20 ft. From 65 ft. to 70 ft. From _____ ft. to 0-20 ft.	
What is the nearest source of possible contamination:	
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well	
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)	
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage None Apparent	

Direction from well?		How many feet?	
FROM	TO	LITHOLOGIC LOG	PLUGGING INTERVALS
0	3	soil	
3	15	brown and tan clay	
15	21	fine to medium sand loose	
21	31	medium to coarse sand and gravel	
31	36	medium to coarse sand & gravel with clay lenses	
36	51	medium to coarse sand and gravel	
51	60	very sand tan clay	
60	77	tan and gray clay	
77	116	medium to coarse sand and gravel	
116	117	red clay	

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 07/02/1997 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This Water Well Record was completed on (mo/day/yr) 07/07/97 Under the business name of Harp Well & Pump Service, Inc. by (signature)
--

Todd S. Harp