

1 LOCATION OF WATER WELL: Sedgwick		FRACTION SW 1/4 NW 1/4 NW 1/4		SECTION NUMBER 27		TOWNSHIP NUMBER T 26 S		RANGE NUMBER R 2W E/W	
Distance and direction from nearest town or city street address of well if located within city? 4020 N. 167th St. W. Colwich, Kansas									
2 WATER WELL OWNER: KLAUSMEYER		Board of Agriculture, Division of Water Resource							
RR#,ST. ADDRESS,BOX #: 4020 N. 167th St. W.		CITY, STATE: Colwich, Kansas		ZIP CODE:		Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: 82 ft. ELEVATION: Depth of groundwater Encountered: ft. WELL'S STATIC WATER LEVEL 30 FT. BELOW LAND SURFACE MEASURED ON 9/30/05 Pump test data: Well water was ft. after hours of pumping @ gpm Est. Yield: gpm Well water was ft. after hours of pumping @ gpm Bore Hole Diameter 12 in. to 82 ft. and in. to ft. WELL WATER TO BE USED AS: ☒ 1. Domestic ☐ 3. Feedlot ☐ 5. Public water supply ☐ 7. Lawn and garden only ☐ 9. Dewatering ☐ 11. Injection well ☐ 2. Irrigation ☐ 4. Industrial ☐ 6. Oil field water supply ☐ 8. Air conditioning ☐ 10. Monitoring well ☐ 12. Other (Specify below) Was a chemical/bacteriological sample submitted to Department? YES ☒ NO ; If yes, what mo/day/yr was sample submitted YES ☒ NO							
5 TYPE OF CASING USED: 1. Steel 3. RPM (SR) 5. Wrought Iron 7. Fiberglass 9. Other (Specify below) CASING JOINTS: ☒ Glued Threaded ☒ 2. PVC ☐ 4. ABS ☐ 6. Asbestos-Cement ☐ 8. Concrete tile SDR-26 ☐ Welded ☐ Clamped Blank casing diameter 5 in. to 62 ft., Dia. in. to ft., Dia. in. to ft. Casing height above land surface: 12 in., Weight: 2.35 lbs. / ft. Wall thickness or gauge No. .214 TYPE OF SCREEN OR PERFORATION MATERIAL: 1. Steel 3. Stainless Steel 5. Fiberglass ☒ 7. PVC 9. ABS 11. Other (specify) 2. Brass 4. Galvanized 6. Concrete Tile 8. RMP (SR) 10. Asbestos-Cement 12. None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1. Continuous slot 3. Mill slot 5. Gauzed wrapped 7. Torch cut 9. Drilled holes 11. None (open hole) 2. Louvered shutter 4. Key punched 6. Wire wrapped ☒ 8. Saw cut 10. Other (specify) SCREEN - PERFORATION INTERVAL From 62 ft. to 82 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 24 ft. to 82 ft., From ft. to ft. From ft. to ft., From ft. to ft.									
6 GROUT MATERIALS: 1. Neat cement 2. Cement Grout 3. Bentonite Other bentonite hole plug Grout Intervals: From 4 ft. to 24 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: 1. Septic tank 4. Lateral lines 7. Pit privy 10. Livestock pens 13. Insecticide storage 15. Oil well/Gas well 2. Sewer lines 5. Cess Pool 8. Sewage lagoon 11. Fuel storage 14. Abandon water well 16. Other (specify below) ☒ 3. Watertight sewer line 6. Seepage pit 9. Feed yard 12. Fertilizer storage Direction from well? Northwest How many feet? 100 ft.									
From To LITHOLOGIC LOG From To LITHOLOGIC LOG 0 4 topsoil 4 15 clay 15 30 fine sand 30 50 coarse sand 50 60 clay 60 82 medium coarse sand									
7 Contractor's or Landowner's Certification: This water well was 1. ☒ constructed 2. reconstructed or 3. plugged under my jurisdiction and was completed on (mo/day/year) 9/30/2005 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This water well record was completed on (mo/day/year) 10-3-2005 under the business name of Harp Well & Pump Service Inc. by (signature) <i>J o d d S. H a r p</i>									