


WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

48043

1 LOCATION OF WATER WELL: County: Sedgwick		Fraction ¼ SW ¼ NE ¼ NE ¼	Section Number 5'	Township No. T 26 S	Range Number R 2 ☐ E ☒ W																																																																								
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☒ 77th St. N and 183rd St. W.			Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																										
2 WATER WELL OWNER: Kevin Seiler RR#, Street Address, Box #: 18505 W. 77th St. N. City, State, ZIP Code : Colwich, KS 67030																																																																													
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N  W E S -----1 mile-----		4 DEPTH OF COMPLETED WELL 115 ft. Depth(s) Groundwater Encountered (1) 30 ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL 30 ft. below land surface measured on mo/day/yr Pump test data: Well water was ft. after hours pumping gpm EST. YIELD 800 gpm. Well water was ft. after hours pumping gpm Bore Hole Diameter 30 in. to 115 ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted Water well disinfected? ☒ Yes ☐ No																																																																											
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 16 in. to 115 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface 12 in., Weight 16 lbs./ft., Wall thickness or gauge No. SCH40 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 55 ft. to 75 ft., From 95 ft. to 115 ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From 20 ft. to 115 ft., From ft. to ft. From ft. to ft., From ft. to ft.																																																																													
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From 3 ft. to 20 ft., From ft. to ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well none-open field Direction from well Distance from well																																																																													
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td>0'</td><td>30'</td><td>Clay</td><td></td><td></td><td></td></tr> <tr><td>30'</td><td>67'</td><td>medium sand</td><td></td><td></td><td></td></tr> <tr><td>67'</td><td>85'</td><td>Clay</td><td></td><td></td><td></td></tr> <tr><td>85'</td><td>93'</td><td>Fine Sand</td><td></td><td></td><td></td></tr> <tr><td>93'</td><td>95'</td><td>Clay</td><td></td><td></td><td></td></tr> <tr><td>95'</td><td>99'</td><td>Medium Sand</td><td></td><td></td><td></td></tr> <tr><td>99'</td><td>102'</td><td>Fine Sand</td><td></td><td></td><td></td></tr> <tr><td>102'</td><td>115'</td><td>Medium Sand</td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td><td></td><td></td></tr> <tr><td></td><td></td><td></td><td></td><td></td><td></td></tr> </tbody> </table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0'	30'	Clay				30'	67'	medium sand				67'	85'	Clay				85'	93'	Fine Sand				93'	95'	Clay				95'	99'	Medium Sand				99'	102'	Fine Sand				102'	115'	Medium Sand																					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																								
0'	30'	Clay																																																																											
30'	67'	medium sand																																																																											
67'	85'	Clay																																																																											
85'	93'	Fine Sand																																																																											
93'	95'	Clay																																																																											
95'	99'	Medium Sand																																																																											
99'	102'	Fine Sand																																																																											
102'	115'	Medium Sand																																																																											
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 06/29/2013 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 238 This Water Well Record was completed on (mo/day/year) 07/03/2013 under the business name of Premier Pump & Well Service Inc. by (signature) [Signature] INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send one copy to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5524. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html																																																																													