

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction NW 1/4 SW 1/4 NW 1/4	Section number 17	Township number T 26 S	Range number R 2 E
2. Distance and direction from nearest town or city: Street address of well location if in city: 1 1/2 W, 3/4 N Colwich				3. Owner of well: Walt Gruenbacher R.R. or street: City, state, zip code: Colwich, Kans. 67030		
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile		Sketch map: open field		6. Bore hole dia. 30 in. Completion date Well depth 97 ft. 6/8/77		
		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary				
		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other				
		9. Casing: Material C-Asb. Height: Above or below Threaded ☐ Welded ☐ Surface 18 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 16 ft. depth Wall Thickness: inches or Dia. ☐ in. to 71 ft. depth Gage No. 314				
		10. Screen: Manufacturer's name Johnson Type Cem-Asb. Dia. 16" Slot/gauze 1/4 Length 26' Set between 71 ft. and 97 ft. Gravel pack? ☒ Size range of material 3/8				
5. Type and color of material		From	To	11. Static water level: ☐ mo./day/yr. 26 ft. below land surface Date 6/1/77		
Topsoil		0	1	12. Pumping level below land surfaces: 38 ft. after 2 hrs. pumping 900 g.p.m. 40 ft. after 4 hrs. pumping 1200 g.p.m. Estimated maximum yield 1200 g.p.m.		
Fine Sand		1	10	13. Water sample submitted: ☐ Yes ☒ No Date ☐ mo./day/yr.		
Sand / Clay		10	20	14. Well head completion: ☐ Pitless adapter 18 inches above grade		
Clay		20	25	15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.		
Med. Gravel		25	40	16. Nearest source of possible contamination: ft. 600 Direction W Type Dam W 1/2 Well disinfected upon completion? ☐ Yes ☒ No		
Clay		40	50	17. Pump: Manufacturer's name Peerless Not installed Model number 1266 HP 30 Volts ☐ Length of drop pipe 70 ft. capacity 1100 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
Good Gravel		50	97	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Irrigation 238 Business name Maize, Ks. License No. ☐ Address Maize, Ks. Signed K. Weninger Date 8/5/77 Authorized representative		
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5